

11-11-11E

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SKELLY OIL CO.

SEC. 11 T. 11 R. 11E

FARM N. D. Fearon

NO. 1

LOC. NW SW NE

TOTAL DEPTH 2904

COMM. 8-22-50

COMP. 9-3-50


SHOT OR TREATED

CONTRACTOR Adkins Drilling Co.

ISSUED 5-5-51

COUNTY Wabaunsee

KANSAS



CASINO

8 5/8" 194' cem. w/135 sx

5 1/2" 2901' cem. w/200 sx

ELEVATION 1128 DF

PRODUCTION Pmp. 84.68 BO
NW

FIGURES INDICATE BOTTOM OF FORMATIONS

shale & shells	200	Producing Formation -
shale & shells	425	Viola Lime 2901 to 2904'
shale & lime	800	Main body of pay 2901-04'
lime & shale	1312	
lime	1526	DST: #1 - 2577'; tool open
shale	1635	2 hrs. good blow through-
lime & shale	1765	out; rec. 110' of muddy
shale	1895	salty wtr & 15' of 21 Gvty.
lime, shale & sand	2156	Oil-Corrected. B.H.P. 824#.
lime & chert	2290	DST: #2-2582'; tool open 1
lime	2343	hr, good blow throughout;
shale	2575	rec. 1046' of salty oil cut
lime	2577	water & 2' heavy oil.
Core No. 1 - Cored from		B.H.P. 420#.
2577'-2582'; Rec. 3' 1"-7"		Little porosity 2901-02'
Fine xyn, dense dolomite		Good porosity & oil sat.
with fair porosity & good		2902-04'
oil saturation.		DST: #3 - 2901'-2904'; tool
1'-5" Fine xyn dolomite,		open 1 hr & 50 min.; rec.
very dense with poor porosity		910 bf clean oil, 27 Corr.
and scattered oil saturation.		and no wtr. B.H.P. 1178#.
Core No. 2 - Cored from 2582'-		Ran Halliburton Electric
2589'; Rec. 2'-11"- 1'-3" lgt		Log to 2904'.
gry to buff fine xyn dense		
dolomite. 9" lgt gry to buff		
medium to coarse xyn dolomite		
with good inter-xyn porosity,		
scattered oil staining.		
11" lgt gry to buff fine xyn		
dolomite with a few large		
scattered		
Some oil staining.		
lime	2835	
lime & shale	2885	
shale	2901	
lime	2902	
lime	2904	
Total Depth		

Tops:

Howard	545
Topeka	608
Lansing	1176
Kansas City	1311
Mississippian Lime	2156
Kinderhook	2343
Hunton	2575
Maquoketa	2831
Viola	2901