

11-11-11E

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock Wichita, Kansas


Company - SKELLY OIL CO.  
Farm - N. D. Fearon No. 4

SEC. 11 T. 11 S. 11E  
NW NW NE

330' fr N.L. 330' fr W.L. of  
NE/4

County. Wabaunsee  
KANSAS

Total Depth. 2910 PB 2905  
Comm. 2-28-51 Comp. 3-11-51  
Shot or Treated.  
Contractor. Adkins Drlg. Co., Inc.  
Issued. 9-8-51



CASING:  
8 5/8" 198' cem. w/150 sx  
5 1/2" 2904' cem. w/175 sx

Elevation. 1132 DF

Production. 360 BOP 24/hrs.

Figures Indicate Bottom of Formations.

sand, shale & shells	35
shale, sand & shells	525
lime, shale & sand	1316
lime	1531
lime, shale & sand	2188
lime & chert	2339
shale	2583
lime	2885
shale	2904
lime	2909
lime	2910
Total Depth PB 2905	

Tops:	
Howard	553
Topeka	617
Lansing	1181
Kansas City	1316
Miss.	2170
Kinderhook	2339
Hunton	2583
Mamoketa	2885
Viola	2904

Producing Formation:  
Viola Lime 2904-2905'

Shot 150 gal. acid between  
2904-2906'

Main body of pay 2904-2905'

DST: #1 - 2904-2909, tool  
open 1 hr. rec. 1500' of  
clean oil, no wtr. BHP 1110#.

Ran Schlumberger Survey to  
2909'