

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas


11-11-11E

Company - SKELLY OIL CO.
Farm - N. D. Fearon No. 5

SEC. 11 T. 11 R. 11E
NW NE NE
330' fr N.L. 1650' fr W.L. of
NE/4

County. Wabaunsee
KANSAS

Total Depth. 2877
Comm. 3-20-51 Comp. 4-1-51
Shot or Treated.
Contractor. Adkins Drlg. Co.
Issued. 9-8-51



CASING:
8 5/8" 215' cem. w/150 sx
5 1/2" 2873' cem. w/205 sx

Elevation. 1106 IF
1108 RB (and)
Production. 529 BO

Figures indicate Bottom of Formations.

sand, lime & shale	225
shale & lime	1060
lime & shale	1485
lime	1502
shale & lime	1645
shale, lime & sand	1895
shale, shells & chert	2055
lime, shale & sand	2161
lime, shale & chert	2293
shale	2528
lime	2534
lime	2553
lime	2655
lime	2820
lime & shale	2872
lime	2877
Total Depth	

Tops:	
Howard	532
Topeka	595
Lansing	1148
Kansas City	1288
Mississippian Lime	2145
Kinderhook	2293
Hunton	2528
Maquoketa	2602
Viola	2872

Producing Formation:
Viola Lime 2873-2877'

Shot 250 qts. acid.

Main body of pay 2873-2877'

DST: #1 - 2529-2534', tool
open 1 hr. rec. 10' slightly
oil cut mud and wtr. BHP 868#.
DST: #2 - 2531-2553' tool
open 1 hr. rec. 900' slightly
brackish water with pin points
of oil BHP 902#.
DST: #3 - 2873-2877' tool open
1-1/2 hrs. rec. 400' of clean
oil, no wtr. Flow. Press. 108#.
BHP 1042#.

Ran Schlumberger Survey to 2877