

11-11-11E

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas


Company - SKELLY OIL CO.
Farm - N. D. Fearon No. 6

SEC. 11 T. 11 S. 11E
NW SE NE

990' frm EL, 990' fm SL, NE 1/4

Total Depth. 2885
Comm. 4-11-51 Comp. 4-21-51
Shot or Treated.
Contractor. Adkins Drlg Co.
Issued. 9-8-51

County. Wabaunsee
KANSAS



Elevation. 1108 DF
110 RB (sand)

Production. 41.76 BO & 41.76 BW

Figures Indicate Bottom of Formations.

shale, lime & sand	100
lime & sand	217
shale & shells	590
shale & lime	910
shale, lime & sand	1161
lime & shale	1305
lime	1507
shale, lime & sand	2153
lime & chert	2318
shale	2555
lime	2810
shale & lime	2881
lime	2883
lime	2885
Total Depth	

Tops:	
Howard	530
Topeka	592
Lansing	1161
Kansas City	1297
Mississippi	2157
Kinderhook	2320
Hunton	2555
Maquoketa	2815
Viola	2881

Producing Formation:
Viola Lime 2882-2885'
Main body of pay 2882-2885'

Ran Schlumberger Survey to 2883'

DST: #1 - 2874-2883'; tool open
15 min., slight blow for 6 min.
then stopped. rec. 4' oil cut mud
& 1 gal. oil No BHP recorded.
DST: #2 - 2879-2883'; tool open
30 min., slight blow 12 min. rec.
15' oil cut mud & 1 gal. oil. BHP 1022#.
DST: #3 - 2878-2885'; tool open
1-1/2 hrs. good blow throughout
rec. 710' of oil and 10' of oil cut
mud. Shut in BHP after 15 min. 1050#.