



1-11-116

Operator Name .. Shawnee Petro., Inc. Lease Name Hund Well# 1 SEC 1 TWP 11 RGE 11

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem test giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached sta level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken [ ] Yes [x] No
Samples Sent to Geological Survey [x] Yes [ ] No
Cores Taken [ ] Yes [x] No

Formation Description
[x] Log [ ] Sample

Heebner - SH
Lansing - LS Tan. sing. micro-Xln. Xln. por. Tr. vein Re-Xln. Firm/dense. No vis. por.
E C - SH Mostly lt. & med. gray/some green-gray. Tr. silty. Tr. silt size SD. Some pyrite
MISS - LS Tan/tan mot/sing. micro/Xf Xln. por. Tr. sucrocic. Vf/f Re-Xln. Some chert: Clr/Wh. semiopaque. Angular. No trip inclusions. Some firm. No/Tr. vis. por.
KIND - SH Mostly grays & blk. Some red (hematitic)/purple, yellow, tan, brn. Tr. silty
HUNT - DOL Tan Micro/Xf Re-Xln. Tr. sucrocic. Firm Tr./tr. fr. vis. por. Tr. lt. gray with depth
VIOL - DOL Mostly tan/lt. & med. gray. Mot./mostly sing. micro/Tr. XF. Xln. F/M Re-Xln. Sub/euhedral Xtals. Tr. vuggy por. Tr./fr. vis. por. Faint odor. V dull sptd. yel. fluor. After crushing, rare blk. dead oil. No gas. Sptd. med. brn. stain. Wk (+) cut/res. (+) acid/res.

Table with columns: Name, Top KB, Bottom. Rows include Heebner (896), Lansing (1146), Base of Kansas City (1482), Mississippian (2153), Kinderhook (2301), Hunton (2535), Maquoketa\* (2802), Viola\* (2879).

\*Rotary depth adjusted to correct electric log depth.

AUG 29 1984

State Geological Survey WICHITA BRANCH

CASING RECORD table with columns: Purpose of string, size hole drilled, size casing set, weight lbs/ft, setting depth, type of cement, # sacks used, type and percent additives. Includes a PERFORATION RECORD section below.