

2-11-11E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.
Farm- M. C. Wagner No. 1

SEC. 2 T. 11 R. 11E
SW SE SE
330 F NL & 990' FEL SE/4

County Wabaunsee
KANSAS

Total Depth. 2865
Comm. 5-21-51 Comp. 5-29-51
Shot or Treated.
Contractor. Addins Drlg. Co.
Issued. 9-15-51



Elevation. 1098 RB (2nd)
1096 DE

Production. 107.88 BO & NW in
8 hrs.

✓
Figures Indicate Bottom of Formations.

shale & lime	110
shale, lime & sand	222
shale & shells	240
shale & lime	1280
lime	1480
shale, lime & sand	2170
lime & chert	2286
shale	2435
shale & lime	2531
lime	2865
Total Depth	

Tops:	
Howard	520
Topeka	583
Lansing	1140
Kansas City	1282
Mississippi Lime	2140
Kinderhook	2282
Hunton	2531
Maquoketa	2794
Viola	2860

Ran Schlumberger Survey to
2865'

DST: #1 - 2859'-2865'; Tool
open 1 hr, strong blow through-
out. Rec. 800' oil and 60'
of oil cut mud. Initial flow.
Press. 35#, BHP 1055#, Finish
pressure 311#.

Producing Formation:
Viola Lime 2861-2865'

Main body of pay 2861-2865'