

20" 10" 1033 FARM Werner NO. 1 COUNTY Shawnee
 15 1-20 8 1-4 1370 COMPANY Holl et al
 12 1-2 271 5 3-16 CONTRACTOR T.L. Russell, Garnett, Kansas
 COMMENCED July 1, 1926. COMPLETED Oct. 10, 1926.


TOTAL DEPTH 2006' SHOT QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Mr. F. G. Holl,
 Wichita, Kansas.

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 11/6/26.

ELEVATION
 INITIAL PRODUCTION Dry



Formation	Depth	Formation	Depth
soil	15	lime light	1123
shale blue	31	shale black	1128
lime bornw	34	lime light	1142
shale blue	60	shale black	1147
lime light	68	shale blue	1158
shale dark	75	lime light	1200
lime light	83	shale dark	1206
shale dark (Show gas)	115	lime light	1252
sand light	133	shale blue	1370
lime light (Water)	135	lime dark	1373
sand	195	shale dark	1381
lime light	198	lime light	1393
shale dark	203	shale black (Cave)	1398
sand brown	250-40	lime light	1400
lime light	260	x shale light	1414
shale dark	320	lime light	1421
shale light	330	shale light	1434
shale dark	380-70	lime light	1442
lime light	395	shale blue (cave)	1456
shale dark	405	lime light	1461
shale light	410	shale	1478
lime	416	lime	1482
shale light	476	shale blue	1495
broken lime light	515	shale sandy	1515
shale dark	533	shale blue	1555
lime brown	543	sand gray	1565
shale gray	588	shale blue	1592
lime brown	615	lime dark	1596
shale dark	621	shale black	1640
lime	625	slate white hrd	1660
shale dark	628	shale dark	1720
lime light (Water)	645-0	shale black (cave)	1748
shale light	685	shale light	1762
shale dark	695	slate dark hrd	1765
shale sandy	700	shale white	1785
shale blue	778	lime dark	1790
sand	784	shale light sandy	1800
shale dark	810	shale black (cave)	1865
shale light	908-2	lime sandy	1868
lime light	931	shale black	1904
shale black	933	lime flinty dark	1919
lime light	947	shale black	1935
shale dark	955	lime light	1940
lime white	960	shale brown	1950
shale white	969	shale black	1965 Pa
lime white	974	flint white (Top Miss.)	1966
shale white	979	sandy lime white (HF)	1975
lime white	985	lime flinty white (Water)	1980
sand white (Hole full)	1029	lime gray	2000
shale blue (Water)	1043-10	limey slate drk	2006
lime light	1054		
shale blue	1059	TOTAL DEPTH	2006