

Company Kleinstieber et al


13-11-23E Plotted
Sec. 13 T. 11 R. 23 E
Loc. NE SW NW NW
480' fr WL, 1900' fr SL

Farm Community Lease No. 1

Total Depth 431
Comm. 5/23/33
Shot or Treated
Contractor
Issued

Comp. 5/29/33

County Wyandotte



Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8 6 1/4" -- 382'
13 3/8	5 3/16

Elevation 912

Production 554,000 cu. ft.
Dry Peru Gas

Figures Indicate Bottom of Formation

soil & clay	8
lime boulders	15
shale	25
lime	51
shale	84
lime	89
shale	90
lime	91
shale black	92
lime	93
shale	102
lime	115
shale	121
lime	132
shale muddy	145
lime	146
shale	148
lime	150
shale	156
lime	163
shale	165
lime little salt water	182
shale some black, gas	188
lime	212
shale black	214
lime water too much to	215
shale SLM 217 OK (carry	216
lime	227
shale	270
sand gas showing	280
shale	300
shale sandy	388
sand SLM 395 OK gas	392
sand hard no gas	398
shale	419
lime	423
sandy lime, gas bubbles at	425
sand Gas 554,000	431
T.D.	

Gas increased steadily from 425'
to T.D. of 431. Packer set at 422'