

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.


Location ~~SE~~ NE ^{SE} NW

Sec. 2 T. 11 R. 14E

Casing Record

County- Shawnee

10" 1368 Farm- Omar Allen No. 1
 20" 8" 2168 Company- Jones, Davisson et al
 15" 42 65/8" Contr.- J. W. Davisson Drlg. Co.
 12" 616 63/16" Comm.- 8-9-29 Comp.- 9-14-29
 Total Depth 2471 Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Elevation 1040

Figures Indicate Bottom of Formations.

Initial Production Dry

Date Issued. 11-2-29

Formation	Depth	Formation	Depth
soil	5	shale gr	1380
quicksand	45	lime	1390
lime wh hrd	50	shale gr	1445
shale blue sft	60	lime	1455
lime W H	65	shale gr	1615
shale gray sft	75	sand	1630
lime wh hrd	80	shale blk	1680
shale gr sft	255	shale gr	1720
lime wh hrd	260	shale blk	1785
shale brown sft 4BW	270	shale gr	1803
lime wh hrd	275	slate blk	1829
shale blk sft	330-7	shale gr	1895
lime wh hrd	340	shale blk	1905
shale bl sft	360	shale drk	2080
sand gr sft HFW 370	390	lime Top Miss.	2140
lime wh hrd	400	sand gr HFW	2150
slate bl sft	420	lime gr	2303
lime wh hrd sdy	435	slate	2450
shale gr sft	500	lime	2462
lime wh hrd	505	sand brown	2468
slate gr sft	520	Sulphur H2O	
lime wh hrd p	530	sand brown	2471
shale drk sft	545	Total Depth	2471
slate bl(8-16-29)	585		
shale bl sft	623		
lime wh sft	650		
shale drk sft	655		
lime wh hrd	660		
shale wh sft	665		
lime wh hrd	675-D		
shale gr sft	755		
shale sdy	765		
shale gr sft 2BW 770	845		
sandgr sft	855		
shale gr sft	905		
lime gr hrd	910		
sand sft	925-L		
lime wh hrd HFW 930	950		
slate wh sft	955		
lime G S	960		
shale G S	970		
lime wh hrd	1005		
shale G S	1045-1120		
lime wh hrd	1060-15		
slate	1070-15		
lime wh hrd	1095		
shale bl sft	1115		
lime wh hrd	1125		
shale wh sft	1130		
lime wh hrd	1145		
shale blk sft	1170		
lime wh hrd	1200		
shale blk sft(8-24)	1205		
lime wh hrd	1215		
shale gr	1220		
lime wh	1270-P&C		
shale gr	1330		
shale bl	1360		
shale gr	1370		
lime wh	1372		

Accounts Report
 1374-77

SAMPLE RECORD


2-11-14E 11-14

State Kansas Co. Shawnee Farm Omar Allen No. 1 Sec. 2 Twp. 11 Rge. 14E

Location _____

Company Jones-Davidson Date Drilled _____

Elevation 1,040' Total Depth 2,471'



Cherokee

1880 Soft gray shale, coal.

1920 Gray sandy shale, dark shale

Mississippi lime

2080 Hard sandy dolomite, hard white chert.

Determinations

Miss. Lime 2080-2305

Kinderhook Chattanooga shale 2305-2450

Hunton lime 2450-2471 T.D.