

20-11-28E Plotted

Company

Sec. 20 T. 11 R. 23E

Farm Longfellow B.S. Oil No. 4
& Gas Co.

loc. NE SW SE

Borden's map 9/9/1930

Total Depth 424

County Wyandotte


Comm.

Comp. 1916

Shot or Treated

Contractor

Issued



Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation

Production 95B.

Figures Indicate Bottom of Formation

soil	3
lime	58
shale	60
lime	115
shale	119
lime	169
slate	175
lime	247
slate blk wtr	252 W
lime	259
slate	266
shale	280
sand gas & oil	290 Knottown gas and oil
lime	294
slate	300
sdv shale	403
sand gas	422 gas
lime	424 T. D.

well showed 34 bbls 1 min.
and 44 cu. ft. in 24 hours.

after blowing 4 or 5 hours; 95 lbs. R.P.