

BONNER SPRINGS OIL & GAS CO.

20-11-23E 21.20 ✓  
 T Plotted

Well Record-Longfellow # 1. Drilled, 1904.

Above Sea Level 932

Sec. 20-11-23.E

Plotted  
 R.S.

3	Soil	yellow	3			
40	Lime	white	43			
11	Shale	light	54			
4	Lime	white	58			
7	Shale	blue	65	12	Sand light, increase of	547
40	Lime	white	105		gas	
10	Shale	blue	115	3	Shale, light	552
4	Shale	black	119	38	Shale, brown	590
18	Shale	light	137	25	Sand, white, little oil	615
28	Lime	white	165	6	Shale, light	621
15	Lime	gray	180	9	Sand, dark	630
13	Clay	blue	193	5	Red Rock, red	635
4	Lime		197	65	Shale	690
3	Shale		200	4	Red Rock	694
5	Lime		205	4	Sand	698
4	Sand, little gas		209	40	Shale	740
10	Lime, dark		219	17	Sand little gas	747
2	Slate, black		221	48	Shale	805
24	Lime, white		244			
2	Slate, black		246			
15	Lime, dark		261			
4	Shale, blue		265			
15	Sand, dark		280			
31	Shale, light		311			
29	Shale, dark		340			
38	Shale, gray		360			
15	Shale, light		375			
5	Sand, light		380			
9	" "		389			
5	Red Rock-red		394			
6	Slate, light		400			
8	Lime, light		408			
12	Sand light		420			
5	Shale "		425			
6	Sand "		430			
9	Shale "		439			
12	Lime, dark		451			
20	Shale, light		471			
4	Lime, dark		475			
4	Slate, blk, little gas		478			
2	dark		480			
22	Shale, white		502			
12	Shale, light		514			
3	Lime dark		517			
4	Slate "		521			
14	Sand, light gas		535			

Well pulled and plugged years ago.

No record of the date.