


RYAN CONSOLIDATED PETRO. CORP.
Laming No. 1.SEC. 22 T. 11 R. 21 E.
6 SW NWTotal Depth. 2033
Comm. 12-20-41 Comp. 3-15-42
Shot or Treated.
Contractor.
Issued. 4-4-42

County Leavenworth

CASING.

12"	180'
10"	1248'
8"	1683
6"	1787
5"	1966



Elevation. 953 L+S

Production. DRY

Figures Indicate Bottom of Formations.

surface	15	shale sdy trace of		shale dark	1217
clay	30	coal	762	sand silica cemented	1226
shale blue	55	sand tight	770	sand trace chert, trace	
shale light	63	shale sdy	775	dead oil stain, no	
shale lime	75	sand tight	780	free oil	1230
shale blue	95	shale blue	796	sand trace chert, trace	
shale	135	shale blk	798	water	1234
sand little water	153	coal	800	chert, tripoli and sand	
lime	179	sand	802	2 BWPH	1236
shale blk	180	shale sdy	808	chert, tripoli and	
lime	220	shale blk	812	sand HFW	1240
shale red	225	sand fine tight	820	cherty dolomite	1248
lime	232	lime	821	cherty dolomite	1265
shale	240	shale sdy	825	dolomite HFW 1300	1286
lime	280	shale dark	847	dolomite cherty	1293
shale gritty	290	lime	853	dolomite lime & chert	1313
lime grey	310	sand siderite	862	dolomite, trace lime	1328
shale blue	330	shale dark	864	lime cherty	1377
lime	332	shale red	867	lime, dolo. chert	1432
shale blk	338	cemented siderite	870	dolomite cherty	1465
lime sdy	353	sand	872	lime, dolo. cherty	1515
lime	375	shale blue	874	dolomite cherty	1538
shale blue	385	shale dark	889	lime and dol. cherty	1572
lime dark	395	lime dark	891	lime trace cherty	1601
shale dark	405	shale dark	926	lime dark	1627
lime	468	sand 1 BWPH	940	shale dark spores	1681
shale	472	shale dark	955	lime dense	1696
lime	495	sand Calcareous	960	lime & dolo. some chert	1729
shale	505	shale blk	992	2 BW 1718, 1BW 1723, HFW 1729	
sand fine	550	sand grey	1005	dolo. some lime & chert	1750
shale blue	590	shale dark	1009	lime trace of sand	1759
shale dark	605	lime brown	1011	lime and sand	1770
lime	622	sand tight	1018	sand	1774
shale dark	640	shale dark	1020	shale chert and	
lime	650	sand grey	1027	tripoli	1777
shale	655	shale dark	1033	lime cherty	1819
lime	660	sand	1037	lime & dolo, trace dead	
coal	661	shale dark	1040	oil stain, no free	
shale dark	665	no record	1050	oil	1928
lime	671	shale	1062	dolo. chert, tripoli	1835
shale blue	672	sand tight	1068	dolo. some lime & chert	1841
lime	674	shale sdy	1080	2 BWPH	
sand shaly	678	sand	1092	dolomite cherty	1851
shale dark	680	shale sdy	1100	dolomite cherty trace	
sand light	686	sand tight	1106	dead oil stain 1BWPH	1855
lime	690	shale dark	1118	cherty dolomite HFW	1860
shale blk	697	shale light	1122	dolomite, trace chert	
sand light	703	sand 1/2 BWPH	1140	very hard	1900
trace gas and water.		shale grey	1147	sand trace shale, slight	
shale blue	706	shale blk	1155	stain, heavy oil & wtr	1904
sand tight	709	lime blk	1157	sand	1966
lime	716	siltstone	1162	dolomite, cherty, trace	
shale blue	725	shale blk	1165	shale, trace asphaltic	
shale dark	747	sand 1 BWPH	1175	stain, no free oil	1969
lime shaly	751	shale dark	1206	1969 equals 1966	
sand	757	shale dark, trace of		dolomite, trace oil in	
		brown lime	1210	sample, no free oil, 2033	
				Total Depth.	