

11-11-22E *Plotted*

Company


Sec. 11 T. 11 R. 22 E

Farm Rutherford

No. 2

Loc. Center SE $\frac{1}{4}$  NE $\frac{1}{4}$

County Leavenworth



Total Depth 492'

Comm.

Comp. 1944

Shot or Treated

Contractor

Issued

Elevation

Production Gas

Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 1/4 349'
13 3/8	5 3/16

Figures Indicate Bottom of Formation

surface	15	
lime	27	
shale	32	
lime	46	
shale	51	
lime	56	
shale	77	
lime	94	
shale	97	
sand	110	SO from 97 to 110
lime	113	
shale	119	
lime	126	
shale	131	
lime	142	
shale	158	
lime	207	
shale	210	
lime	214	Little water from
shale	223	210 to 214
lime	233	
shale	239	
lime	249	
shale	268	
lime	272	
shale	275	
lime	302	
shale	308	
lime	332	
shale	335	
lime	347	BKC
shale	357	
Sand broken	377	
shale	392	110,000 <sup>CF</sup> gas from KBT
sand	424	
shale	449	392-424
lime	452	
sand	457	SO 452-457 Hcp
shale	483	
lime	487	
shale	492 TD	

Hole plugged back to 424  
Packer set at 389  
110,000 gas from 392 to 424  
Rock pressure 105#