

31-4-22E

Plotted

LEAVENWORTH COUNTY KANSAS

#2 Pierce Atlas Ter. Co. (Kaw Pipeline Co.)

NE/4 SW/4 Sec. 31, Twp. 11, R. 22E

Sproul and Young Contractors (Lawrence, Kansas)

Gas Well

Comm. 9-9-1924

Log of gas well drilled on Dr. Pierce farm 5 miles NE of Linwood, Kan

3	soil	3
9	sandstone	12
25	lime	37 Set 8 1/2 at 18'
4	shale	41
4	slate blk	45
1	lime	46
5	shale	51
4	lime	55
4	shale	59
2	lime	61
9	shale	70
22	lime wh	92
24	shale bl	116
9	lime	125
1	shale bl	126
62	lime wh	188
4	shale bl	192
5	lime bl	197
6	shale bl	203
3	lime bl	206
14	shale bl	220
15	lime	235
7	shale	242
14	lime wh	256
8	shale	264
10	lime wh	274
4	shale bl	278
22	lime	300
5	shale bl	305
25	lime	330
3	slate blk	333
17	lime	350
2	SAND	352
6	shale	358
10	SAND light	368
5	shale bl	373
93	shale sdy	466
4	lime	470
4	shale wh	474
4	slate blk	478
4	shale red	482
10	shale	492
4	shale	496
3	lime	499
10	shale	509
6	shale bl	515
2	shale	517
5	lime hd wh	522
8	shale dark	530
10	lime	540
10	shale wh	550
2	lime	552

BKC
KBT

KBT

Gas water

8	shale bl	560
5	lime	565
7	shale dark	578
6	lime	578
8	shale wh	586
8	shale dark	594
2	lime wh	596
15	shale dark	611
1	shale dark	612
6	lime	618
2	lime wh hard	620
4	SAND and shale	624 Set 4 7/8 at 623'
18	SAND	642 GAS

Set 643' tubing
Packer set 617'

423 ft. 4 1/2"
 492 ft. 6 1/4 casing
 18 ft 8 1/4 casing
 643 ft. tubing
 Packer set 6 ft up
 in casing.
 Casing set in middle
 of sand.
 42 ft. stone.
 22 ft Lime white

Set 6 1/2 at 492' 6 1/4 casing