

WICHITA BRANCH
KANSAS DRILLERS LOGAPI No. 15 — 209 — 20,006
County Number

Operator

L. Beal

Address

4001 Kaw Drive Kansas City, Kansas 66102

Well No.

#1

Lease Name

Beal

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

F.E. Young Drilling Co.

Geologist

Spud Date

6/30/'77

Total Depth

463'

P.B.T.D.

Date Completed

7/7/'77

Oil Purchaser


S. 18 T. 11 R. 25 E W

Loc. NE NE NW

County Wyandotte

640 Acres

N



Locate well correctly

Elev.: Gr. 850'

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
		6 1/2"		0-21'			

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Dry Hole	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Beal Co.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name Beal Co.	Dry Hole	
S <u>18</u> ^S <u>11</u> ^E <u>25</u> ^W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
surface	0	2	
clay yellow	2	58	plugged 25', 5 sacks
clay blue	58	60	
gravel pea and smaller, ½GPM water	60	65	
shale dark grey	65	69	
lime lt. grey	69	77	
shale blue-grey	77	98	Hertha
sandstone brown no gas noticed	98	100	plugged 100', 10 sacks
shale blue-green	100	108	
sandstone grey-green	108	116	
shale grey, sandy	116	146	
sandstone light grey	146	162	
shale grey	162	190	
lime black, soft	190	191	
shale green 2-3GPM water	191	200	
sandstone light grey	200	208	
shale red	208	214	
sandstone light grey	214	221	
shale grey	221	242	
lime grey, soft	242	244	
shale grey	244	260	
lime light grey	260	268	
shale black	268	270	Worland
lime light brown	270	273	
shale grey	273	283	
lime brown	283	289	
shale grey	289	307	
lime grey	307	312	Lexington
shale black, slaty, no gas	312	316	
sandstone light green	316	319	
lime light grey	319	321	
shale grey	321	330	
lime dark grey	330	333	
shale light green	333	361	
lime brown, soft	361	364	
shale black	364	375	
shale sand light grey	375	462	
lime light grey	462	463	Dry Hole bottom in lime
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	Signature Title Date		

476251