

25-11-8E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.
Farm- Yeage No. 8

SEC. 25 T. 11 R. 8E
NE NW SW

Total Depth. 1678'
Comm. 8-6-59 Comp. 8-13-59
Shot or Treated.
Contractor. White & Ellis Drig. Co.
Issued. 7-30-60

County Riley
KANSAS



CASING:

8 5/8" 225' w/175 sx cem.
5 1/2" 1665' w/100 sx cem.

Elevation. 1326' RB (5' Above
G.L.)

Production. 48 B O- tr wtr.-
24 hrs. P.O.

Figures indicate Bottom of Formations.

11 Meas fr R.B.

lime	20	Lansing Ls	1170
shale	30	Base	1253 N.S.O.
lime	65		
colored shales	75	Kansas City Ls	1268
lime	110	Base	1504 N.S.O.
colored shales	125		
lime	130	Pawnee Ls	1523
lime, 3 BW	140	Base	1534 N.S.O.
shale	155		
lime, HFFW	170	Fort Scott Ls	1539
shale	205	B se	1580 N.S.O.
lime	225		
shale	238	Penn. Sh. Congl.	1610
shale, shells	362	Base	1621 N.S.O.
lime, shale stks	375		
shale, lime	540	Hunton Ls	1621
shale, shells	650	Pen.	57 G.S.F.O. below 1665'
lime	662		
shale	710		
lime	731	DST #1 -1658-78'	
shale	779		
lime, shale stks	920	Core #1 - 1640-60'	
shale, lime stks	963	" #2 - 1662-68	
lime	997	" #3 - 1669-78'	
lime w/shale	1171		
lime	1242	Ran Schlumberger Laterlog	
lime, shale stks	1269	and Sonic.Log.	
lime, hd. stks	1305		
shale	1309	Top Good oilzone is 1665-78	
lime	1580		
shale	1620		
lime, c hatty stks	1640		
lime	1678		
Total Depth			

TOPS:

Topok Ls	705
Base	735 N.S.O.
Deer Creed Ls.	780
Base	821 N.S.O.
Lecompton Ls	843
Base	880 N.S.O.
Oread Ls	963
Base	1006 N.S.O.
(Huebner Sh. 996-1004')	
Douglas Sh.	1006
Base	1170 N.S.O.

Steel Line Meas.

S.H.S.

1012' = 1012'
1495' = 1395' Strapped drill pipe.
1516' = 1516' 1516' O.K.