

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock,
Wichita, Kansas

25-11-8E


Company- CITILS SERVICE OIL COMPANY
Farm- Gehrt No. 2

SEC. 25 T. 11 R. 8E
NE SW NW

Total Depth. 1660'
Comm. 8-5-59 Comp. 8-12-59
Shot or Treated.
Contractor. White & Ellis Drlg. Co.
Issued. 3-19-60

County Riley

KANSAS



Elevation. 1222' KB

Production. Temp. Abd.

CASING:

8 5/8" 232' cem. w/200 sx.
5 1/2" 1660' Cem. w/100 sx.

Figures indicate Bottom of Formations.

lime	15	Top Pennsylvania Conglomerate	
colored shales	25		1505.5
lime, soft	35		
shale, dark	55	Top Hunton	1529
lime, H.F.F.W.	70		
shale & shells	115	DST #1 1529-1556' ISIT 30 min.	
lime	125		
shale	135	DST #2 1553-1586' (33' anchor)	
lime	155		
shale	190	DST #3 1579-1601' (22' anchor)	
lime	205		
shale	210	DST #4 1601-1615' Misrun.	
lime	230		
shale w/lime strks.	335	DST #5 1598-1615' (17' anchor)	
shale & shells	595	ISIT for 30 min.	
sand	618		
lime & shale strks.	815	DST #6 1615-1630' (15' anchor)	
shale & lime strks.	946	ISIT for 30 min.	
shale	1050		
sand & shale	1078	Core #1 1505-1520' (15') (Rec. 14')	
lime	1160		
sand & shale	1178	Core #2 1520-1535' (15') (Rec. 15')	
lime	1411		
shale	1422	Core #3 1538-1547' (9') (Rec. 9')	
lime	1442		
shale	1449	Core #4 1547-1555 (8') (Rec. 8')	
lime	1484		
shale	1505	Core #5 1556-1561' (5') (Rec. 5')	
shale & lime	1527		
lime	1660	Core #6 1561-1571' (10') (Rec. 9 1/2')	
Total Depth		Core #7 1571-1586' (15') (Rec. 15')	
TOPS:			
Top Topeka	627	Core #8 1586-1601' (15') (Rec. 15')	
Base	650		
		Core #9 1601-1615' (14') (Rec. 14')	
Top Deer Creek	692		
Base	706	Core #10 (15') (Rec. 12') 1615-1630'	
Top Lecompton	757		
Base	797		
Top Oread	880		
Top Hoebner	912		
Base Hoebner	922		
Top Douglas	1014		
Base	1078		
Top Lansing	1078		
Base	1160		
Top Kansas City	1177		
Base	1411		
Top Pawnee	1425		
Base	1442		
Top Fort Scott	1449		
Base	1496		