

22-11-8E ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- O. F. PRAHL  
Farm- Barry No. 1

SEC. 22 T. 11 R. 8E  
SE NE NE

Total Depth. 1659'  
Comm. 7-19-65 Comp. 10-21-65  
Shot or Treated.  
Contractor. White & Ellis  
Issued. 12-4-65

County Riley  
KANSAS



CASING:

Elevation. 1102' KB

8" 215' cem w/ 150 sx  
5" 1656' cem w/ 75 sx

Production. 7 BOPD NW

Figures Indicate Bottom of Formations.

*Yaeger Field?*

Penn sand	1556
conglomerate chert	1584 show free oil & odor
chert	1604 good oil staining
chert	1612 free oil & odor
no log	1659
Total Depth	

TOPS:	SMP	LOG
Topeka		737
Heebner	945	943
Toronto	958	955
Lansing	1123	1122
Kansas City	1223	1220
Pennsylvania sand	1548-56	1546-56
Conglomerate	1566	1562
Mississippi	1575	1584
Hunton	1631	1620

DST # 1 1575-1604 tool open 1 hr, had a good blow & rec. 270' clean oil. ICIP 575 p.s.i., 15 min; IFP 66 P.s.i., FFP 122 p.s.i., FCIP 481'p.s.i. 30 min.