


SEP 29 1972

DRILLERS LOG



23-11-8E

SW SW NW
API# 15-161-20011
Elevation: 1161' KB
IP: P 25 BOPD & Wtr./Miss.

OPERATOR: Skyline Oil, Inc.

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Wallace Well No. 1

Sec. X 23 T. 11S R. 8E Spot Approx. SW SW NW

County Riley State Kansas Elevation 1161' KB

Casing Record:

Surface: 8 5/8" @ 304' with 200 Sxs. 3% cc

Production: 5 1/2" @ 1553' with 65 Sxs.

Type Well: Oil Total Depth 1582'

Drilling Commenced: 5-22-72 Drilling Completed 5-25-72

Formation	From	To	Tops
Cellar & Sod	0	30	
Gravel	30	60	Mississippi 1551
Lime	60	150	
Shale w/Lime (Stks.)	150	880	
Lime	880	920	
Shale	920	1037	
Sandy Lime	1037	1083	
Shale	1083	1095	
Lime-	1095	1130	
Lime & Shale	1130	1551	
Lime	1551	1582	

LOG TOPS:

Heebner	926
Lansing	1093
Cherokee Shale	1508
" Sand	1512
Mississippi Cht	1551
" Lime	1572



COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation _____ Perforated Interval _____ Number Shots _____