

25-11-8E ✓

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- CITIES SERVICE OIL CO.
Farm- Gehrt No. 5

SEC. 25 T. 11 R. 8E
SW SE NE


Depth. 1720'

3-20-63

Comp. 4-5-63

County Riley

KANSAS



or Treated.

Dr. White & Ellis Drlg.

9-14-63

CASING:

8 5/8" 225' cement w/400 sx.
5 1/2" 1720' cement w/150 sx.

Elevation. 1312' DF

Production. 37 BO - 132 BW/20hrs
(Hunton)

58 BO-NW 24-hrs/(Penn. Cgl.
Sd.)

Figures indicate Bottom elevations.

lime	45
shale	50
red rock	60
lime	65
shale	75
lime	100
shale	110
red rock	115
lime	125
shale, blk.	130
lime	210
red rock	215
shale	220
lime	225
shale	375
lime & shale strks.	520
shale & shells	612
shale	650
shale & lime	710
lime	745
lime & shale	886
shale	970
lime	1016
shale & shells	1078
sand & sandy shale	1171
lime	1257
shale	1276
lime	1509
shale	1526
lime	1601
shale & sand strks.	1650
sand	1658
lime	1720 RTD

Base Lansing	1258
Kansas City	1276
Base Kansas City	1510
Pawnee	1533
Ft. Scott	1552
Base Ft. Scott	1587
Conglomerate	1601
Conglomerate Sand	1648
Hunton	1658

Total Depth

TOPS: LOG

Lecompton	845
Oread	971
Muebner	1002
Douglas	1015
Douglas Sand	1043
Lansing	1170