

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


25-11-8E

Company- CITIES SERVICE OIL COMPANY
Farm- Yaeger No. 7

SEC. 25 T. 11 R. 8E
SW SW SE

Total Depth. 1696'
Comm. 7-21-59 Comp. 7-29-59

County Riley
KANSAS



Shot or Treated.
Contractor. White & Ellis Drig. Co., Inc.
Issued. 3-19-60

Elevation. 1375 DF

Production. 56 BOPD - 0 Wtr.

CASING:

8 5/8" 230' cem. w/125 sx.
5 1/2" 1668' cem. w/100 sx.

Figures indicate Bottom of Formations.

lime	15	Top Pawnee Limestone	1564
shale	30	Base	1578
colored shales	35		
lime	45	Top Ft. Scott	1588
shale	85	Base	1625
lime	90		
shale & shells	115	Top Pennsylvania Conglomerate	
red rock	120		1644
lime	130		
shale & shells.	160	DST #1 1663-1676' ISIT 30 min.	
shale	165	Open 1 hr. FSIT 30 min.	
lime.	170		
shale	180	DST #2 1676-1696' ISIT 30 min.	
lime H.F.W.	185	Open 1 hr. FSIT 30 min.	
shale	190		
lime	230	Ran Schlumberger Logs.	
shale & lime	645		
shale & shells	699	Core # 3 1676-1686' (10') (Rec. 9')	
lime	709	Core #4 1686-1696' (10') (Rec. 10')	
shale w/lime strks.	764		
lime	785		
shale & shells	829		
lime	943		
shale	1019		
lime	1056		
shale & lime strks.	1157		
sd. shale	1216		
lime	1546		
shale & shells	1572		
lime & shale	1653		
Core #1	1665		
Core #2	1676		
Core #3	1686		
Core #4	1696		
Total Depth			
		Top Lecompton	891
		Base	934
		Top Oread Limestone	1019
		Top Heebner Shale	1050
		Base Heebner Shale	1059
		Top Douglas	1099
		Top Lansing Limestone	1215
		Base	1297
		Top Kansas City Limestone	1313
		Base	1546
Core #1 1653-1665' (12') (Rec. 12)			
Core #2 1665-1676' (11') (Rec. 10 1/2')			
TOPS:			
Top Topeka Limestone	764		
Base	786		
Top Deer Creek	828		
Base	841		