

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

25-11-8E


Company- CITIES SERVICE OIL CO.
Farm- Yaege No. 13

SEC. 25 T. 11 R.8E
SW NE SE

Total Depth. 1650'
Comm. 11-19-60 Comp. 12-14-60
Shot or Treated.
Contractor. White & Ellis Drlg.
Issued. 5-6-61

County Riley

KANSAS



CASING:
8 5/8" 225' cem w/170 sx.
5 1/2" 1644' cem w/100 sx.

Elevation. 1322' KB

Production. 102 BO - 2 BW-24 hrs.

Figures indicate Bottom of Formations.

lime	40
red rock	50
lime	75
shale	85
lime	115
shale	118
lime	130
shale	140
lime	155
shale	160
lime	175
shale	185
lime	200
shale	205
red rock	210
shale	220
lime	225
shale & lime	585
sandy shale	697
lime	731
shale w/lime strks	879
shale	960
lime & shale	992
shale, sdy.	1166
lime	1240
lime & shale	1265
lime	1497
lime & shale	1643
lime & dolomite	1650 RTD
Total Depth	

Base Douglas Sh. & Sd.	1116 NSO
Lansing Ls.	1166
Base Lansing Ls.	1248 NSO
Kansas City Ls.	1265
Base Kansas City Ls.	1500 NSO
Pawnee Ls.	1517
Base Pawnee Ls.	1530 NSO
Fort Scott Ls.	1540
Base Fort Scott Ls.	1575 NSO
Penn. Sdy. Sh. Congl.	1600
Base Penn. Sdy. Sh. Congl.	1643 NSO
Hunton Ls.	1643
Pen.	7' G.S.F.O.

Ran Schlumberger electric logs.

Steel Line Measurement	SHS
1571' = 1571'	1571' O.K.

TOPS:

Topeka	697
Base Topeka	730 NSO
Deer Creek Ls.	770
Base Deer Creek Ls.	787 NSO
Lecompton Ls.	833
Base Lecompton Ls.	877 NSO
Oread Ls.	960
Heebner Shale	992-1001'
Base Oread	1006 NSO
Douglas Sh. & Sd.	1006