

25-11-8E ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE PETROLEUM CO.
Farm- Yaeger No. 14

SEC. 25 T. 11 R. 8E
SW NW SW

Total Depth. 1705'
Comm. 5-17-61 Comp. 6-14-61
Shot or Treated.
Contractor. White & Ellis Drilg. Co.
Issued. 9-8-62

County Hiely
KANSAS



Elevation. 1373' KB(5' ab. G.L.)

Production. 127 B0-17 BWPD

CASING:

8 5/8" 255' w/115 sx cem.
5 1/2" 1685' w/125 sx cem.

Figures indicate Bottom of Formations:

All Meas. fr. K.B.

soil	5
lime	15
shale	20
red rock	25
lime	35
shale	50
lime	65
shale	80
lime	90
shale	100
lime	140
shale	150
lime	170
shale	180
lime	190
shale	195
lime	210
rec rock	215
shale	220
lime	230
shale	235
lime	240
shale	250
lime	255
shale, shells	350
shale, lime stks	920
lime	942
shale	1014
lime	1047
shale	1090
shale, shells	1188
sand	1226
lime	1526
shale, lime stks	1539
lime	1557
shale, lime stks	1576
lime	1617
shale, lime stks	1674
conglomerate	1684
lime	1705
Total Depth	

Hunton Dol. 1674
(More Cgl. fr. 1677-1684')
Main Hunton Sec. 1684
Pen 21'

No electric log run.

D.S.T. #1 1685-1705' open
1 hr. Fair blow in 18 min.,
decreased to vy. weak blow.
Rec. 90' oil & 20' drilg. mud.
I.B.H.P. 548#/30"; I.F. 20#;
F.F. 45#; F.E.H.P. 468#/30".

Steel Line Meas.	S.H.S.
1030' - 1030'	1030' 10'
1499' - 1499'	1499' 10'

TOFS:
Oread Ls. 1014
Heebner Sh. 1046-1055
Base Oread 1058 N.S.O.

Kansas City Ls 1323
Base 1526 N.S.O. noted.

Pawnee-Ft. Scott Ls. 1576
Base 1632

Conglomerate 1651