

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
505 East Murdock, Wichita, Kansas

26-11-8E


Company- CITIES SERVICE OIL COMPANY
Farm- Yaeger No. 10

SEC. 26 T. 11 R. 8E
NE SE NE
1660' S & 330' W of
NEo NE SE NE
County Riley

Rotating bit 1688'
10-28-59 Comp. 11-3-59

Shut in/Produced:
White & Ellis Drilling Co.
9-17-60

KANSAS



Elevation. 1315' RB

Production. 10 BOPD

8 5/8" @ 230' w/100 sks. cem.
5 1/2" @ 1670' w/125 sks. cem.

Figures indicate Bottom of Formations.

lime	15	Pawnee Limestone	1525
colored shale	20	Base Pawnee	
shale	30	Limestone	1541
lime	45	Fort Scott	
shale	70	Limestone	1549
colored shale	80	Base Fort Scott	
lime	90	Limestone	1593
shale	110	Conglomerate	1606
colored shale	125	Hunton Limestone	1634 1634
lime	140		
shale	150		
lime, hole full of fresh water	170	Drill Stem Test	
shale & shells	215	#1	1635-1650 (15' Anchor)
lime	230	#2	1655-1670 (15' Anchor)
shale & shells	405	#3	1670-1688 (18' Anchor)
shale & lime strks.	570		
shale & shells	650		
lime	653		
shale & shells	720		
shale & lime strks.	760	Core #1	1600-1620 (20') (Rec. 18')
shale & shells	796	#2	1621-1636 (15') (Rec. 15')
shale & lime strks.	905	#3	1638-1649 (11') (Rec. 11')
shale	1195	#4	1650-1656 (6') (Rec. 6')
lime	1370	#5	1656-1670 (14') (Rec. 14')
shale	1419	#6	1670-1676 (6') (Rec. 6')
lime	1422	#7	1677-1687 (10') (Rec. 10')
lime, hard strks.	1448		
shale	1452		
lime, hard strks.	1475		
lime	1507	Ran Schlumberger Laterolog &	
shale	1550	Microlaterolog.	
lime & shale strks.	1600		
lime	1688	RTD	
Total Depth			

TOPS:

SCOUT
TOPS

Topeka Limestone	722	
Base Topeka Limestone	754	
Deer Creek Limestone	796	
Base Deer Creek Limestone	842	
Lecompton Limestone	864	
Base Lecompton Limestone	904	
Oread Limestone	992	
Base Oread Limestone	1050	
Douglas Shale	1050	
Base Douglas Shale	1190	
Lansing Limestone	1190	1189
Base Lansing Limestone	1262	
Kansas City Limestone	1276	
Base Kansas City Limestone	1507	1508