

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


26-11-8E

Company- CITIES SERVICE PETROLEUM CO.
Farm- Yaeger No. 15

SEC. 26 T. 11 R. 8E
NE NE SE

Total Depth. 1740'
Comm. 6-28-61 Comp. 7-8-61
Shot or Treated.
Contractor. White & Ellis Drlg.
Issued. 9-23-61

County Riley KANSAS



Elevation. 1403' KB

Production. 104 BO - 104 BW/24 hrs.

CASING:

8 5/8" 270' cem w/200 sx.
5 1/2" 1719' cem w/125 sx.

Figures indicate Bottom of Formations.

lime	30
shale	35
red rock	40
lime	50
shale	70
red rock	75
shale	85
lime	110
shale	125
red rock	130
lime	165
shale	175
red rock	180
lime	185
shale	200
lime	210
shale	220
lime	240
shale	250
lime	255
shale	265
lime	270
shale & shells	495
lime	580
shale & shells	935
shale & lime strks	1035
shale & shells	1060
lime	1092
shale & lime strks	1259
lime	1504
shale & lime strks	1605
lime	1617
shale	1624
lime	1670
shale	1719
lime	1740 RTD
Total Depth	

No electric log run.

DST #1 1720-1740' ISI 30 min, op 1 hr, FSI 30 min. Weak blow thruout. Rec. 50' clean oil, (31° A.P.I. corr.) 10' M.C.O. & 60' O.C.M. (Total 120') IBHP 485#, IF 35#, FF 60#, FBHP 355#, still building.

<u>Steel Line Measurements</u>	<u>Straight Hole Survey</u>
529' = 529'	529' O.K.
998 = 998'	998' O.K.
1496 = 1496'	1496' O.K.

TOPS:
Topeka Ls. 805
Base 827 NSO
Deer Creek Ls. 869
Base 910 NSO

Lecompton Ls.	934
Base	974 NSO
Oread Ls.	1060
Base	1106 NSO
Douglas Sh.	1106
Base	1260 NSO
Lansing Ls.	1260
Base	1328 NSO
Kansas City Ls.	1354
Base	1585 NSO
Pawnee Ls.	1605
Base	1617 NSO
Fort Scott Ls.	1624
Base	1670 NSO
Penn. Conglomerate	1688
Base	1719 NSO
Hunton Dol.	1719
Pen.	21' F.-G.S.O.