

KANSAS State Geological Survey

IMPORTANT
Kans. Geo. Survey request
samples on this well.


WICHITA, BRANCH

API No. 15 — 061 — 20,007
County Number

S. 33 T. 11 R. 8 E

Loc. SW SW NW

County Geary

640 Acres
N

Locate well correctly

Elev.: Gr. 1461'

DF KB

Operator

Barnett Oil Company

Address 411 First National Bank Building
Wichita, Kansas 67202

Well No.

#1

Lease Name

Green

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Alco Drilling Co.

Geologist

John E. Brewer

Spud Date

11/14/73

Total Depth

1983'

P.B.T.D.

Date Completed

11/14/73

Oil Purchaser

- -

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9"	8 5/8"	28#	205'	Common	118	4 sks CaCl
Production	7 7/8"	5 1/2"	9.5#	1983'	Portland Pozmix "A"	25 25	1 sk Halco gel 4 sks 18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			24 holes		1936-44
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gals. acid; Frac w/20,000 gals. water; 11,000# sand	1936-44

INITIAL PRODUCTION

Date of first production None		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Barnett Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole		
Well No. 1	Lease Name Green			
S 33 T 11 R 8 E XXX				
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil & clay	1	18	B/Oread	Sample
Lime	18	65	Iatan	1290 (+171)
Lime & shale	65	203		1385 (+ 76)
Shale w/lime streaks	203	311		LOG
Lime	311	330		
Shale w/lime streaks	330	368	Lansing	1451 (+10)
Lime	368	373	Cherokee	1870 (-409)
Shale	373	561	Conglomerate	1916 (-454)
Red bed	561	568	Miss. Chat	1934 (-473)
Shale	568	619	Miss. Lime	1960 (-499)
Shale w/lime streaks	619	747	T.D.	1965
Lime	747	786		
Shale	786	926		
Lime	926	931		
Shale	931	944		
Lime	944	953		
Shale	953	990		
Lime	990	1023		
Shale	1023	1064		
Lime	1064	1087		
Shale w/lime streaks	1087	1131		
Lime	1131	1173		
Shale	1173	1232		
Shale w/lime streaks	1232	1241		
Lime	1241	1273		
Lime w/shale streaks	1273	1282		
Shale	1282	1284		
Lime	1284	1298		
Sandy shale	1298	1454		
Lime	1454	1534		
Shale	1534	1548		
Shale w/lime streaks	1548	1560		
Lime w/shale breaks	1560	1655		
Shale, Lime & Lime & shale	1655	1914		
Shale w/lime streaks & red bed	1914	1928		
Chat rough	1928	1941		
Lime & chat	1941	1954		
Miss. Lime	1954	1962		
Shale	1962	1983		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
		BARNETT OIL COMPANY By: <i>[Signature]</i> Partner Title Date: April 23, 1974		
		Signature Title Date		
		Signature Title Date		
		Signature Title Date		