

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

36-11-8E


Company—CITIES SERVICE OIL COMPANY
Farm—Koepsel No. 1

SEC. 36 T. 11 R. 8E
NW NW NE

NE NW NE *Top*

County Riley

KANSAS



Total Depth. 1695'

Comm. 8-26-59

Comp. 8-29-59

Shot or Treated.

Contractor. White & Ellis Drlg. Co.

Issued. 3-5-60

CASING:

10 3/4" 234' cem. w/125 sx.

8 5/8" 1678' cem.w/100 sx.

Elevation. 1381 K.B.

Production. 33 oil -tr. wtr.
PD

Figures Indicate Bottom of Formations.

limestone	20		
red rock	25	S.L.M.	S.H.S.
limestone	55	1008' - 1008'	1008' O.K.
shale	70	1500' - 1500'	1500' O.K.
limestone	95	1670' - 1670'	1670' O.K.
shale	100		
colored shales	110		
shale & shells	170		
shale, blk.	175		
shale, gy.	180		
limestone	210		
shale	230		
limestone	233		
shale & shells	243		
shale & limestone strks.	380		
shale & shells	475		
shale & limestone strks.	1015		
limestone	1045		
shale	1211		
limestone	1305		
limestone, hd. strks.	1413		
limestone, dk. shale	1432		
limestone	1542		
shale w/limestone	1599		
limestone & shale strks.	1667		
limestone, hd. strks.	1695		
Total Depth			

TOPS:

Top Lecompton	883
Base	926
Top Oread	1014
Base	1060
Top Lansing	1210
Base	1290
Top Kansas City	1306
Base	1542
Top Pawnee-Ft. Scott	1566
Base Fort Scott	1622
Top Hinton Farm	1676

DST #1 1679-1695' S.I. 1/2 hr., open 1 hr., S.I. 1/2 hr., fair blow for 15 min., decreasing to weak for duration of test, no gas to surface, rec. 90' fluid, being 60' free oil, 30' oil cut Rotary mud, I.B.H.P. false; F.B.H.P. 550#; I.F. 25#; F.F. 45#; I.E.S.H. 840#; F.H.S.H. 840#; Temp. 92°. Grind out 31.5° corrected, .4 of 1% wtr. & mud.