

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

36-11-8E

Company- CITIES SERVICE PETROLEUM CO.
Farm- Koepsel No. 6

SEC. 36 T. 11 R. 8E
NE SW NE

Total Depth. 1761'

Comm. 7-6-61

Comp. 7-12-61


Shot or Treated.

Contractor. White & Ellis Drlg.

Issued. 9-30-61

County Riley

KANSAS



CASING:

10 3/4" 245' cem w/125 sx.
5 1/2" 1740' cem w/125 sx.

Elevation. 1414' KB

Production. 60 BO & 155 BW/24 hrs.

Figures Indicate Bottom of Formations.

soil	5
lime	15
shale	20
red rock	25
lime	45
shale	50
lime	60
shale	70
red rock	75
shale	80
lime	125
shale	130
red rock	135
lime	190
red rock	195
shale	200
lime	210
shale, blk	215
shale	225
lime	245
shale & lime strks	540
shale & shells	792
lime	821
shale & lime	1015
shale	1053
lime	1093
shale	1206
sand	1257
lime	1337
shale & shells	1357
lime	1590
shale	1611
lime	1622
shale	1627
lime	1666
shale & lime strks	1729
lime	1761
Total Depth	

Pen.

32'

1729-40' V.S.S.O.
1740-50' G.S.O.
1750-60' S.F.O.
1760-61' S.S.O.

No electric log run.

DST #1 1730-1740', (10' anchor)
ISI 30 min, op 1 hr, FSI 1 hr.
No blow. Rec. Non.
IBHP 75#, IF 5#, FF 5#, FBHP 255#.

DST #2 1740-1750' (10' anchor)
ISI 30 min. op 1 hr, FSI 30 min.
Fair blow thruout. Rec. 130' clean
oil (32.4° A.P.I. corr.) 15' drlg.
mud. (Total rec. 145') IBHP 550#,
IF 10#, FF 60#, FBHP 435#.

TOPS:

Tope ka Ls. 792
Base 811 NSO
Deer Creek Ls. 865

'Base	
Lecompton Ls.	908 NSO
Base	929
Oread Ls.	971 NSO
Base	1053
Douglas Sd.	1103 NSO
Base	1133
Lansing Ls.	1257 NSO
Base	1257
Kansas City Ls.	1337 NSO
Base	1357
Pawnee Ls.	1587 NSO
Base	1607
Ft. Scott Ls.	1622 NSO
Base	1627
Penn. Cgl.	1666 NSO
Base	1698
Hunton Dol.	1729 NSO
	1729

1845

Casing Record

8 5/8

245' Cemented
w/200 sacks

5 1/2

1740' Cemented
w/125 sacks

T.D.

1750'

Kelly Bushing Measurement 5' above ground level.

FORMATION

DEPTH

Soil
Lime
Shale
Red rock
Lime
Shale
Lime, L.C.Z.
Shale
Red rock
Shale
Lime
Shale
Red rock
Lime
Red rock
Shale
Lime
Shale, blk.
Shale
Lime
Shale & Lime stks.
Shale & Shells
Lime
Shale & Lime
Shale
Lime
Shale
Sand
Lime
Shale & Shells
Lime
Shale
Lime
Shale
Lime
Shale & Lime stks.
Lime

0-5
15
20
25
45
50
60
70
75
80
125
130
135
190
195
200
210
215
225
245
540
792
821
1015
1053
1093
1206
1237
1337
1357
1590
1611
1622
1627
1666
1729
1750

TOPS

Douglas
Lansing

1206
1257

Kansas City
Pawnee

1357
1611

Ft. Scott
Hunton

1627
1729

Plan: ONE SW NE

Section: 36-11S-8E

Riley County, Kansas

Farm: Koepsal #6

Well Owner: ~~C. J. Koepsal~~ **OXY USA INC.**

Contractor: White & Ellis Drig., Inc

Spudded: 7/6/61

Under Surface: 7/10/61

Completed: 7/13/61

K C C
MAY 03 1991

RECEIVED
WICHITA CORPORATION COMMERCIAL

MAY 2 1991

CONSERVATION DIVISION
Wichita, Kansas