


*Plotted
 8-11-23E
 Albert Wheeler*

ARROW OIL & GAS CO.
 McKee No. 1.

SEC. 8 T. 11 R. 23E
 SE NE NW
 2470' E WL 1390' S NL

Total Depth. 512'
 Comm. 8-6-30 Comp. 8-21-30
 Shot or Treated.
 Contractor.
 Issued. 5-15-37

County. Wyandotte



CASING:
 6 5/8" 366'
 4 7/8" 498'

Elevation. 996

Production. 560,000 cu ft
 gas. RP 140#

Figures Indicate Bottom of Formations.

soil	7
sandstone	38
shale <i>wtr</i>	40
lime	44
shale	51
lime	64
shale	69
lime	73
shale	82
lime	87
shale	94
lime	110
shale	130
lime	162
shale	177
lime	214
shale	215
lime	221
shale blk	222
lime	226
shale	235
lime	248
shale	252
lime	261
shale	277
lime	278
shale	280
lime	283
shale	287
lime	293
shale	296
lime <i>wtr</i>	315
shale	321
lime	343
shale	345
lime	348
shale	350
lime <i>SLM-366</i>	361
shale	408
sand	411
shale	458
sand <i>dry</i>	463
sand <i>gas bubbles</i>	473
lime	477
shale grey	483
red bed	489
lime sdy	493
sand gas	511
shale	512
Total Depth. <i>Shale</i>	514