

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-11-9E

Company- GEORGE F. JOHNSTON, JR.  
Farm- Durein "B" No. 1

SEC. 15 T. 11 R. 9E  
NW SW SE

Total Depth. 1452'  
Comm. 4-18-62 Comp. 4-22-62  
Shot or Treated.  
Contractor. D.D. Sandlin  
issued. 6-2-62

County Riley  
KANSAS



Elevation. 1390' RB

Production. DRY

CASING:

7" 60' w/21 sx cem.

Figures Indicate Bottom of Formations.

- 909-950 Shale, gray, red; fine, silky,  
micaceous sandstone.
- 950-1010 Sandstone, gray, micaceous, fine  
grained, no odor, no stain.
- 1010-1015 Limestone.
- 1015-1064 Shale gray, stringer of thin  
limestones, gray, very fine  
grained, shaley sandstone.
- 1381-1400 Limestone sense, thin shale  
streaks.
- 1409-1438 Limestone, dense; shale strks.
- 1438-1445 Weathered, white to pale brown  
quartz, pyritic, micaceous,  
trace feldspar, increasing  
last 5 feet.
- 1445-1452 Material as above, increase in  
pink granite and feldspar.

Total Depth

TOPS:

Howard	571
Topeka	615
Deer Creek	683
Lecompton	748
Clay Creek	849
Oread	861
Heebner	888
Douglas	909
Lansing	1064
Kansas City	1167
B/Kansas City	1358
Marmaton	1381
Pawnee	1409
Weathered Granite	1438
Solid Granite	1445