

9-11-23E

Company Bonner Springs Oil & Gas Co.

Sec. 9 T. 11 R. 23E

Farm Holyfield

No. 1

Loc. SWc NE

County Wyandotte

Total Depth


Comm. Nov 16, 1916

Comp.

Shot or Treated

Contractor

Issued



Casing

20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation

Production

Figures Indicate Bottom of Formation

Above sea level 1004.51'

3	soil	3	3	shale	503
34	sand water	37	6	slate	509
5	lime dark	42	5	sand	514
10	shale	52	30	shale	544
20	lime	72	5	lime	549
25	shale	97	10	sand gas	559
16	lime	123	9	shale dark	568
11	shale	134	19	sand gas	587
26	lime	160	1	shale	588
2	shale	162			
45	lime	207			
7	shale	214			
4	lime gas	218			
1	slate black	219			
4	lime	223			
10	shale lime shell	233			
12	lime	245			
6	shale	251			
14	lime	265			
6	shale	271			
5	lime	276			
6	shale	282			
7	lime	289			
2	shale	291			
9	lime	300			
3	shale	303			
14	sandy lime gas in top	317			
6	slate black	323			
27	lime	350			
3	shale	353			
10	lime	363			
30	shale	393			
5	sand gas	398			
45	shale	443			
20	sand water	463			
12	shale	475			
5	sand	480			
8	red rock	488			
2	lime	490			
10	red rock	500			

900' from this well an old well had been drilled years ago and was cased and closed in but was never packed. This likely allowed the gas to spread through the sands above and let the water into the sand below. This well only worked a few days until it filled with water and quit making gas.