

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas


18-12-11E

Company - SKELLY OIL CO.
Farm - A. W. Wolgast No. 1

SEC. 18 T. 12 R. 11E
SE NE SW
990' fr N.L. & 2210' fr W.L. of SW/4

County, Wabaunsee

KANSAS



Total Depth. 3168
Comm. 1-10-51 Comp. 1-22-51
Shot or Treated.
Contractor. Adkins Drlg. Co.
Issued. 8-25-51

CASING:

8 5/8" 195' cem. w/150 sx
5 1/2" 1727' cem. w/75 sx

Elevation. 1254 DF

Production. Dry

Figures Indicate Bottom of Formations.

shale & lime	50
shale, lime & shells	100
shale, lime & shells	208
shale & shells	275
lime & shale	1506
lime	1679
lime	1685
lime	1718
lime, sand & shale	2378
lime & chert	2669
shale	2842
lime & chert	2852
lime	3094
shale & lime	3166
lime	3168
Total Depth	

Tops:	
Howard	724
Topeka	791
Lansing	1369
Kansas City	1506
Miss. Lime	2378
Kinderhook	2669
Hunton	2842
Maquoketa	3094
Viola	3166

DST: #1 1674-1679'; tool
open 1 hr, weak blow throughout;
rec. 8' of oil cut mud and 1
gal. of Green oil, No. BHP reading
due to instrument failure.

Good porosity 1679-1685'
DST: #2 - 2839'-2852'; tool
open 1 hr, rec. 33' of water
& mud with scum of oil. BHP 25#.

DST: #3 - 3164'-3168'; tool
open 1 hr. rec. 110' very
slightly brackish water, no oil.
BHP 1135#.

Ran Schlumberger Survey to 3168'

1-27-51 Shot 2000 gal. acid
between 1674-1685'