


SAGAMORE OIL & GAS CO.  
David Williams No. 1.

SEC. 31 T. 12 R. 19 E  
CNW NW  
660'S 660'E NW 1/4

Total Depth, 1680'  
Comm. 5-11-42 Comp. 6-16-42  
Shot or Treated.  
Contractor. S.R. McKinney  
Issued. 7-11-42

County. Douglas



CASING:

12" 11' P 6 5/8" 1526' P  
10" 428' P 53/16" 1630' P  
8" 962' P

Elevation. 1072 (1073)

Production. Dry

Figures Indicate Bottom of Formations.

soil & clay	12	lime	1000
lime	17	shale	1013
shale	22	lime	1014
sdv shale	27	shale	1020
shale	43	shale sdy	1075
lime	46	shale	1105
shale	85	sand HFW	1155
lime	92	shale	1165
shale	95	lime	1170
lime	115	shale	1199
shale	120	shale sdy	1205
lime	123	shale gy	1215
shale	131	shale dk	1250
lime	148	shale gy	1256
shale	297	sand	1266
lime	302	shale dk 1HW 1260	1300
shale sdy	317	shale gy	1328
shale	331	shale sdy	1344
shale sdy	345	lime	1347
shale	385	shale dk	1365
sand HFW	413	shale & sand	1376
lime	421	shale dk	1381
shale	428	sand	1387
lime	446	sdv shale	1400
shale	451	sand HFW	1421
lime	457	shale dk	1435
shale	482	sand & shale	1441
lime	502	shale dk	1471
shale	530	lime	1473
lime	568	shale dk	1491
shale	603	shale gy	1498
lime 2 1/2 HW 610	634	shale dk	1523
shale	642	sand lime & chert	1542
lime	655	lime & flint	1619
shale 1 1/2 HW 660	668	brown lime blue	
lime	725	flint	1630
shale	731	lime brown	1670 W
lime	775	lime sdy	1680
shale	820	Total Depth.	
sand	830		
shale	883		
sand	893		
shale	914		
shale brown & green	927		
lime	935		
shale	937		
lime	940		
shale	959		
lime	964		
shale	978		
lime	984		
shale	987		
lime	993		
shale	998		

413  
59