

pany Small & Magee

Farm Charlton

No. 1

Sec. 14 T. 12 R. 20E

Loc. SE NW NE

County Leavenworth

14-12-20

Total Depth 783 (1/2)


Comm. 7/17/22

Comp. 8/1/22

Shot or Treated

Contractor

Issued



Casing

20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation	4 7/8 20" packer
	Set at 758
Production	8 1/4 casings 21'
	6 1/4 " 185'
	4 7/8 " 705

Figures Indicate Bottom of Formation

clay yellow	27	
lime	32	1st sand 490-500
clay yellow	50	2nd sand 510-535
shale brown	100	3rd sand 776-783
shale sdy wtr 130	120 (Water at 130)	
lime	185	
shale blk	200	
lime	230	
shale blk	235	
lime	250	
shale	315	
lime	360	
shale	375	
lime wh	385?	
shale wh	385?	
lime	395	
shale	485	
lime wh	490 Gas at 496	
shale wh gas 496	500	
good	515 gas Eudora sand	
shale brown	545	
lime	550	
shale sk	560	
lime	680	
sand blk wtr	687 Black Water	
lime	694	
shale wh	695	
shale blk	725	
shale wh	750	
lime	758	
shale sdy, little gas	762 Little gas	
sand	783 good gas, no record 765-783	

Total Depth.

776- Good gas