

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Plotted acw

Company - SLOAN & ZOOK CO.
Farm - Hill No. 1

SEC. 15 T. 12 R. 20 E
NW NWA NW
330' location

Total Depth. 1210=1214' SLM
Comm. 7-26-45 Comp. 8-10-45
Shot or Treated.
Contractor. Harry Leamon
Issued. 9-22-45

County. Leavenworth
KANSAS



Elevation. 867rh

Production. Dry

CASING:

10" 150'
8 1/4" 772' SLM

Figures indicate Bottom of Formations.

clay	20	No shows of oil or gas
sand & gravel	40	No wtr in Miss. lime @
shale sdy	75	Total Depth., 1210
sand, water	145 - L	sand line measurement
lime	160	& 1214' steel line
shale	165	measurement.
lime	170	
shale	185	Well dry & abandoned.
lime	205	
shale	230	
lime	305	
shale	325	
lime	335	
shale	340	
lime	355	
shale	370	
lime	455	
shale drk	460	
lime	470	
lime sdy	480 - BKC	
shale	585	
534=535 SLM		
sand	595	
shale	600	
red rock	605	
shale	635	
lime	645	
shale	650	
lime	655 -	
shale	660	
sand	670	
shale & sand	675 -	
shale	680	
lime, hrd	683	
2 BWPB 683-90'		
shale drk	690	
lime	700	
shale	725	
lime	730 -	
shale	745 - ch	
shale sdy	765	
1 BWPB 745-65'		
shale	830	
770=772' SLM		
lime	834	
shale	925	
sand DRY	930	
shale	985	
shale sdy	995	
2 BWPB 985-95'		
shale	1075	
sand DRY	1085	
shale	1206	
lime	1210 - M	

1210=1214 SLM

Total Depth.