

Plotted down
35-12-20E

FORRESTER ET AL.
~~Altenborn No. 1.~~
Altenbernd

SEC. 35 T. 12 R. 20E
~~SE SW NW~~
SW SW
CEL SW NW
County Douglas

Total Depth. 1605.
Comm. 6-5-40 Comp. 12-4-40
Shot or Treated.
Contractor.
Issued. 6-7-41



CASING.

10" 89'
8 1/2" 651'
65/8" 1104'

Elevation. 813.6

Production. DRY.

Figures Indicate Bottom of Formations.

sand & shale	81	shale	627
shale blk	85 - < ?	shale	631
lime	99	show oil and HFW	657-62
shale	105	shale blk	643
lime	123	sdv shale	657
shale	156	sand	662
lime	221	sdv shale	668
shale	244	sdv lime	677
lime	249	sdv shale	692
shale blk water	251	shale	710
lime	253	lime	714
shale	269	lime sdv shale	720 - show
lime	280	sdv shale	726
shale	300	shale	759
lime	304	lime	761
shale	305	shale	775
lime	318	red rock	777
shale	322	sand	780
lime	355	sdv shale lime	797
shale blk	357	sdv shale	799
lime	390	shale blk	805
water 375		sdv shale	815
shale	392	sdv lime	828
lime	394 - etc	shale	839
shale	396	shale and lime	844
shale and sand	435	sdv shale	849
shale	438	shale	850
sdv lime	450	sdv shale	858
shale	481	sdv lime	867
lime	483	shale	878
shale	510	shale lime	883
sand & shale	514	sdv lime	891
sdv lime	518	sdv shale	896
shale	537	shale	906
lime	541	shale lime	910
shale	544	shale	924
lime	546	sdv shale	932
red rock	548	shale	946
shale gr.	555	sdv shale	977
lime	590	shale blk	982
shale	593	shale & lime	987
lime	596	shale	996
shale	601	sdv shale	1004
lime	605	sand	1023
shale blk	615	shale	1045
lime	620 - ch	sdv shale	1055
shale	625	lime	1056

1104
115.6
29.2
Base KC - 394' - f
base Pleasanton 535
base Cherokee 1102
top. Miss 1102
Dev 1561'

Top Miss lime 1104

