

11-12-21E

Plotted 0

Leavenworth County, Kansas
#3 Shoenlaber

Bonner Springs Gas Co.
Sec. 11 Twp. 12 R. 21E
960' f EL
260' f SL SE $\frac{1}{4}$

300,000' Gas Well
190 Lbs. R. P.
Elev. 868

8	soil	8	
21	lime	29	SW SE SE
3	shale bl	32	
7	lime	39	
8	shale grey	47	
3	lime	50	
8	shale gray	58	
14	lime	72	Set 10"-77'
25	shale gray	87	
31	lime	128	
3	shale gray	131	
55	lime	186	Water 180'
4	shale bl	190	
10	lime	200	
13	shale bl	213	
13	lime	226	
7	shale bl	233	
27	lime	260	
11	shale and lime	271	
4	lime	275	
3	shale black	278	
5	SAND	283	Gas Bubbles
17	lime	300	
4	shale blk	304	
22	lime	326	
4	shale blk	330	Water
16	lime	346	
2	shale blk	348	
-6	lime	354	
11	shale	365	
94	SAND	369	
91	shale gray	460	Gas Bubbles
28	shale bl	494	Set 6 $\frac{1}{4}$ " 378'
4	SAND	498	Gas
8	shale	506	
6	shale blk	512	Gas show
15	shale bl	527	
7	lime sdy	534	
16	shale gray	555	
7	shale blk	562	water
5	lime	567	SLM
45	shale gray	612	
10	shale broken	622	Set 4 7/8"-622'
7	shale green	629	
12	SAND	641	Gas T. D.