

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 412 Union National Bank Bldg, Wichita, Kansas.

*Plotted acc*  
 14-12-21E

JONES ET AL.  
 Harry J. Smith No. 1.


SEC. 14 T. 12 R. 21E.  
 SW NE SE

Total Depth. 1085  
 Comm. 7-21-39 Comp. 8-10-39  
 Shot or Treated.  
 Contractor.  
 Issued. 6-21-41

County Leavenworth.

CASING.

10" 60'  
 8 1/4" ~~297~~ 327  
 6 1/4" 545' reamed 708'



Elevation. 804, L.S.

Productions GAS.

Figures Indicate Bottom of Formations.

soil and clay	30	shale sdy	623
sand	50 wtr	lime sdy	633 wtr
sand and gravel	58 - L	shale	668
lime	77	lime	673
shale	87	shale	734
broken lime	107	shale light blue	748
shale	111	shale blue	765
lime chalky	147	shale grey sdy	780
shale partly green	157	shale dark	800
red mud	159	shale sdy	932
lime	174	lime shale	940
shale Partly green	190	shale blk	950 little water.
lime	200	shale blk limy	962
shale	204	sand	967
lime	206	shale	1000 - M
shale	211	Miss lime	1085
lime	243	Total Depth.	
shale blk	251 gas bubbles.		
lime	273		
shale	277 little gas.		
lime	280 - RKC		
shale grey	283		
sand	294		
shale	320		
sand water	365 mostly broken		
shale	372		
sand	376		
shale	390		
sand	404		
shale sandy	456		
slate blk	460 wtr		
shale blk	485		
shale light	495		
shale grey	500		
lime	523		
shale	534		
lime	535 - 2L		
slate blk	538		
shale dark	550		
lime sdy	554		
shale blk	563 Gas.		
slate and lime	578 Gas.		
slate and sand	588 Gas.		

Well plugged back to 604.  
 Plate packer set at 552.  
 2" tubing from 604 up to top  
 of ground 1" bleeder lime  
 used.