

JENNINGS DRILLING COMPANY

7001E JENNINGS

P.O. Box 1340 • Lawrence, Kansas 66044

Circle 26 on Reader Service Card

Phone

913-749-1131

Completion Report
2 Irick

800' FNL & 2300 FEL
NE/4 7-12S-21E

- June 27, 1982 Great Guns Ran Collar and Cement Bond logs with portable mast.
- June 28, 1982 Moved tools from Linn Co. after shutting in Webber.
- June 29, 1982 Great Guns on location at 10:00 AM. Checked collars and shot 690 to 94 two shots per foot. Gas to surface after casing swabbed down. Some gas cut water. Tried to measure. TSTM. Ran swabb in fifteen minutes. Got 20' of water. Loaded hole with gear pump. Shot 672 to 676. Swabbed down. No visible increase in gas cut of water. Gas to surface still TSTM. Truck left for another job. Shut down for lunch. Down 12:00 to 1:00. Strung in swab. Had 400' of water in hole. Swabbed down. Put on gauge. 20# in 12" 25# in 15" 30# in 18". Shut down for nite.
- June 30, 1982 Had 220# SICP. Pulled 160' of water. Water had considerable rotary mud. Gas had increased. Gauged with Merla tester 17 MCF. Shut in for one hour. Had 160' of salt water. Caught sample. Great Guns arrived at noon. Loaded hole. Shot 651 to 655 and 659 to 663. Set plug at 668. Swabbed down. Gas to surface TSTM Ran swab. No water. Went to lunch. Ran swab no water. Shut in with gauge. 10# 7" and 20# in 18". Sent truck after two 18 gal. carboys of 15% HCL. Spoted 36 gallons of acid on bottom. Loaded hole. Shut in control head.
- July 1, 1982 SICP 120 #. Water down over 30'. Swabbed hole. Gas cut water and half bl. raw acid. Gas to surface. TSTM. Left well open one hour. Making a little water, not enough to swabb. Will shut in for nite. If pressure on casing high in morning will run siphon. There is half a barrel of acid back in the sand. well will not be in condition to make further assesments until we get all this back.

We have never completed a squirrel well up here that boomed in like the Knobtown on the # 1 Irick. The sand is not as clean and the permability is not near as good. I will discuss Stimulation with Bill Covert when I get some hard facts. This will take all week-end at least.