

7-1222E

Plotted

Well #2

Harbaugh (~~Hopkins~~) 40

Leavenworth Co.

sec. 7, T. 12, R. 22E

CWL SE NE NW

2100 FWL 1000 FNL

905

Cen w L. SE NE NW

soil	5	
sandrocks	40	
shale	45	
lime	77	
black shale	82	
lime	87	
sandy shale	95	
lime	103	
blue shale	113	
lime	128	
blue shale	145	
lime	170	
blue shale	174	
lime	245	
black shale	248	
lime	250	
shale	260	
lime	280	
dark shale	290	
lime	303	
shale	307	
sandy lime	325	
lime	345	
shale	350	
lime	368	
shale	370	
hard lime	376	
black shale	377	water
lime	390	
white shale	415	
gas sand (Eudora)	430	(300,000 cu. ft.)
oil sand	440	
shale	570	
lime	572	
dark shale	578	
lime	580	
dark shale	585	
lime	588	
light shale	606	
lime	609	
black shale (water)	620	
lime	622	
shale	625	
lime	627	
blue shale	650	
white shale	665	6 1/4 casing
white shale	671	
gas sand	687	TD

Well tested 1,400,000 cu. ft.

Harold Dick Contractor

Kansas Geological Survey

R. C. Moore