

Drilled By Herbert Peterson ✓
36-12-23 E 0

Company Universal Oil and Gas Company

Farm Dangelmarer No. 2

Total Depth 673

Comm.

Shot or Treated

Contractor

Issued


Comp. July, 1917

Sec. 36 T. 12 R. 23

Loc. ~~800 feet from S line~~
~~100 feet from W. line~~

SW $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$

County Johnson



Casing

20 in.	10 in.
15 1-2	8 1-4
12 1-2	6 5-8
13 3-8	5 3-16

Elevation

Production Gas 1,250,000
200 lbs. pressure

Figures Indicate Bottom of Formation

Surface sand and gravel	20	
Lime	40	
Break ?	45	Water
Lime	70	
Shale	75	
Lime	110	
Shale	115	
Lime	130	
Shale	140	
Lime	150	
Sandy shale gas	250	
Red shale	265	
Salt sand and white sand	320	
Shale	325	
Lime	365	
Black shale	375	Water and gas
Lime	380	
White shale	385	Caving
Shale	465	
Sand	495	Gas
Shale	570	
Lime	578	
Coal	586	
Red shale	600	
Sand	610	
Shale	630	
Sand	640	
Lime	645	
Coal	650	
Lime	655	
Shale	673	
Coal	673	T.D.