

25-12-23E

State Geological Survey

WICHITA, BRANCH

Y

Bartlesville, Oklahoma

January 26, 1939

Mr. G.H. Baird,  
Room 510-B,  
Office,

In re: Plug Orlando Rose #1 Rose,  
Sec. 25-12-23E., Craig Field,  
Johnson County, Kansas.



Dear Sir.:

Following is the log for Rose #1 showing all the data we have on the well:

Loc. 1280'N-80'W of SE Cor. SW $\frac{1}{4}$

IP dry  
Elev. 1013 (Potter)

Dr. Comm.  
Dr. Comp. 1922

Casing Record:  
8 $\frac{1}{4}$ " 470

FORMATION RECORD:

lime	105	shale	536
lime	130	sand, gas & wtr.	546
shale	155	shale	556
lime	167	lime	560
shale	192	lime	565
lime	207	shale	575
shale	211	red rock	581
lime	273	shale	586
shale	285?	lime	592
lime	310	shale	609
blk. shale, wtr.	313	lime	617
lime	336	white shale	649
shale	343	blue shale	708
lime	355	lime	718
shale	470	shale	738
red rock	484	lime	740
shale	494	shale	790
lime	504	lime	796
shale	509	shale	806
lime	521		

RECOMMENDATION: Clean out to 720 and plug  
cement 720 to 650  
mud 650 to 600  
cement 600 to 450  
mud 450 to 360  
cement 360 to 250  
mud 250 to 15  
cement 15 to below plow depth  
mud over top

Yours truly

C.C. Hoffman

CCH\*lm  
cc: FDF  
RMS  
HP-2

MAY 23 1939

MAY 23 1939