


Plotted by H.C. Dyer
26-12-23 E

Company
Farm A. J. Walker
(Gas) No. 1

Sec. 26 T. 12 R. 23
Loc. SEc NW $\frac{1}{4}$

Total Depth 623
Comm. 7-9-23
Shot or Treated
Contractor Earl Smith
Issued
Comp. 7-14-23

County Johnson



Casing
20 in. 10 in.
15 1-2 8 1-4 18'
12 1-2 6 5-8
13 3-8 5 3-16

Elevation 963

Production

Figures Indicate Bottom of Formation

Soil		3'	Shale	Dark	452
Lime	Shell	19	Lime		456
Lime		35	Gas & sand		460
Shale	Dark	38	Lime		468
Lime		42	Shale	Dark	471
Shale	Blue	85	Lime	FT. Scott	474
Lime		105	Shale	White	478
Slate	Green	115	Rock	Red	490 Cased
Lime		121	Lime		492
Shale	Dark	126	Slate	Black	502
Lime		140	Shale	Grit	507
Shale	Blue	158	Shale	White	517
Lime	Guitts	191	Shale	Light blue	529
Black slate & gas		195	Shale	White	542
Lime		215	Shale	Dark	564
Dark slate & gas		220	Shale	Light	580
Lime		222	Top of sand		580
Slate	Dark	224	Gas & sand	Squimel	622
Lime	Hertha	233	Shale	Black	623 bottom of hole.
Shale	White	242			
Gas & sand		248			
Sandy blue shale		296			
Sand & gas		308			
Shale	Light	328			
Sand & water		338			
Shale	White	346			
Lime		349			
Shale	Sandy	367			
Slate	Dark	370			
Rock	Red	375			
Slate	Dark	410			
Lime		415			
Slate	White	418			
Lime		422			