

Company

Farm Joe Dangelmaier

No. 3

1000-~~NL~~ 200-~~EL~~ ~~NW~~¹/₄ Sec. 35 T. 12 R. 23

~~NW~~ Loc. *SE 1/4 NE 1/4 NE 1/4*
35-12-23 E

County Johnson

Total Depth 520'


Comm. 10-13-26

Comp. 10-22-26

Shot or Treated

Contractor Earl Smith

Issued



Casing

20 in.	10 in.	
15 1-2	8 1-4	Drive Pipe 15'
12 1-2	6 5-8	379'
13 3-8	5 3-16	

Elevation

Production Open flow test 85,000
Rock Pressure 145 LBs.

Figures Indicate Bottom of Formation

Surface	6'	Red rock	365
Gravel(Water)	12	Dark shale	370
Lime	21	Lime	372
Light shale	33	Black shale	379
Lime	36	White shale	390
Lime water & gas	50	Blue shale	400
Dark shale	53	White sandy shale	430
Lime	71	Blue shale	438
Dark shale	75	Blue lime	440
Lime	95	Dark sandy shale	451
Black slate	99	Sand & gas	458
Lime	102	Dark sandy shale	490
Blue shale	106	White shale	495
Lime	114	Dark shale	503
Blue shale	117	White shale	515
Red rock	121	Dark shale	520
Blue shale	131		
White shale	140	Cage set at	454'
Sandy shale	220	6 1/4 packer at	422'
Lime	222	All casing pulled.	
Sand	232		
Light shale	245		
Red rock	251		
Dark shale	265		
Red rock	269		
Lime	271		
White shale	290		
Dark shale	292		
Lime	293		
Shale	294		
Brown Lime	298		
Shale	300		
Lime	303		
Light shale	309		
Lime	315		
Light sandy shale	325		
Dark shale	331		
Lime	337		
Black slate	342		
Sand	352		
White shale	357		