

15-091-13-12-24E
15-091-20095

State Geological Survey

WICHITA BRANCH
authorized service
sales on easy terms



F. E. YOUNG DRILLING CO.

6355 Robinhood Lane
Merriam, Kansas
Ph: HE 2-2772

EAYVET CO.
P.O. Box 390
Shawnee, Ms. 66201


MEANE NW
T12s Sec15
R24e Johnson Co.

15-125-24E


air rotary
begin: 7-8-'77
finish: 7-13-'77
plugged: 7-14-'77 9:00am-3:00pm

total depth: 715'
plugged: 25', 175', and 365'



TYPE AND COLOR OF MATERIAL	FROM	TO	COMMENTS
surface	0	1	
clay yellow	1	10	
lime yellow and white	10	29	plugged 25' 5 sacks
shale black	29	31	
lime grey	31	34	
shale blue	34	46	
lime grey	46	47	
shale grey	47	55	
lime grey	55	70	
shale green	70	75	
shale red	75	79	
shale blue	79	97	
lime brown	97	100	
shale grey	100	115	
lime white	115	118	
shale grey	118	134	
lime brown	134	155	
shale grey	155	191	plugged 175' 10 sacks
lime grey	191	205	
sandstone brown	205	206	
shale grey	206	218	
lime white	218	230	
shale grey	230	233	
lime white	233	245	
shale grey	245	268	
lime grey	268	276	Winterset
shale black	276	277	
lime white	277	305	
shale black slate	305	310	
lime grey	310	330	Bethany
shale black slate	330	334	
lime grey	334	336	
shale grey	336	339	
lime grey	339	347	Hertha
shale grey	347	354	Trace
sandstone green	354	362	gas at 360' -- plugged 365' 5 sacks



BALANCED-FLOW



PERMA-FLOW



JET-O-MATIC



15 125 24E


authorized service
sales on easy terms



F. E. YOUNG DRILLING CO.
6355 Robinhood Lane
Merriam, Kansas
Ph: HE 2-2772

BAYVET CO.
page 2



TYPE AND COLOR OF MATERIAL	FROM	TO	CONTENTS
shale dark grey sandy	362	420	plugged 365' 5 sacks
shale green	420	490	300 gal. water in hole ^{Tues} All
shale red	490	493	
sandstone green	493	494	
shale grey	494	505	
sandstone brown	505	510	
shale grey	510	520	
lime grey	520	525	
shale grey	525	538	
lime brown	538	544	
shale grey	544	565	
lime white	565	568	
shale black slate	568	574	Lexington
lime grey	574	576	
shale grey	576	580	
shale red	580	584	
shale grey	584	625	
shale greenish	625	715	



BALANCED-FLOW



PERMA-FLOW



JET-O-MATIC



15 123 24E

authorized service
sales on easy terms




F. E. YOUNG DRILLING CO.


6355 Robinhood Lane
Merriam, Kansas
Ph: HE 2-2772

Bayvet Log Con't.

shale grey	494	505	
sandstone brown	505	510	
shale grey	510	520	
lime grey	520	525	
shale grey	525	538	
lime brown	538	544	
shale grey	544	565	
lime white	565	568	
shale black slate	568	574	Lexington
lime grey	574	576	
shale grey	576	580	
shale red	580	584	
shale grey	584	625	
shale greenish	625	715	Total Depth



BALANCED-FLOW




PRIME-FLOW



PERMA-FLOW



SHALLOW-FLOW



JET-O-MATIC



SILENT-FLOW