



SOUTH YAEGE PROSPECT

**RUPE OIL COMPANY**

MAAS #1 - SW SE NW of Section 27-12S-9E, Wabaunsee County, Kansas

~~MOSCH-465 DM~~

---

Drilling Contractor: Alco Drilling Co., Inc.  
Iola, Kansas

Geologist: William G. Clement  
Wichita, Kansas

---

December 3, 1973 - Filed "Intent to Drill" with State Corporation Commission.  
Ordered staking and elevation to be run by Laughlin-Simmons & Co.

December 11, 1973 - Laughlin-Simmons staked location and run elevation.  
Elevation is 1304 Ground level.

December 13, 1973 - Bulldozing a road and preparing to move in Rotary Tools.

12/11/73 - Lucille/Laughlin-Simmons called - location staked and elevation run  
1304' Ground level.

Bob had LeRoy Reuter who lives  $1\frac{1}{2}$  miles SE of location take him into location via his jeep.

Location falls (very muddy) - in pasture land without cattle and 400' West of large pond.

best way is  $2\frac{1}{2}$  mi. West of SW/corner of Sec. 27 and to get to this point - it is 8.3 mi North of K-177 from Alta Vista turnoff (at that point is Flag Stop Sign by Xmas Tree Farm)  $2\frac{1}{2}$  Mi. East on good gravel to Laughlin-Simmons "flagging" then 1 mi. East on trail -- only to point mentioned above.

Will need "cat" to get in and out of location. Very, very muddy.



SOUTH YAEGE PROSPECT

**RUPE OIL COMPANY**

JAMES MESEKE #1 - SE NE SW of Section 27-12S-9E, Wabaunsee County, Kansas

---

Drilling Contractor: Alco Drilling Co., Inc.  
Iola, Kansas

Geologist: William G. Clement  
Wichita, Kansas

---

December 16, 1973 - Changed the Well name from Maas #1 to Meseke #1 as Mr. Meseke is owner.  
Moving in Rotary Tools.

December 17, 1973 - Drilled 9" Surface hole--broke down.

December 18, 1973 - Ran 306' of 7" Surface Casing.

December 19 & 20, 1973 - Waiting on Cementers. Shut down because of "blizzard"  
Will cement Surface Casing on the 21st and start up again  
after the Holidays. Cemented 306' Surface Casing with  
75 sacks Cement on 21st.

January 2, 1974 - Drilling Contractor called advising due to the severe cold weather and  
additional snow (15 degrees below this morning) will be a few days  
before they will be back in drilling.

January 8, 1974 - Drilling Contractor advised started drilling out from under surface casing  
at 7:00 p.m. last night(1/7/74). At 2:00 a.m. this morning drilling at  
600'.

January 9, 1974 - Drilling at 1579' at 1:00 p.m. today

January 10, 1974 - Drilling at 1640' at midnight. Estimated Ground Elevation 1300'  
Geologist is out on the Well. Snow, sleet storm in process last  
night and today--very cold. Top of HEEBNER 1275' or -25'  
Top of LANSING 1499' or -199'

January 11, 1974 - Drilling at 1825' at midnight last night. 5 degrees below zero there this  
morning--sun shining. Top of KANSAS CITY 1609' -309'  
Base of KANSAS CITY 1821' -521'

January 14, 1974 - Revised Sample Tops after Laughlin-Simmons ran elevation of 1284' Ground  
and 1288' Kelly Bushing on 1,

Top of HEEBNER	1275'	+9'
Top of LANSING	1499'	-215'
Top of KANSAS CITY	1619'	-335'
Base of KANSAS CITY	1841'	-557'

Rotary Total Depth...2380'

The #1 Meseke ran 800' low to the Wells to the West. This is rather  
conclusive evidence that the "test" was on a low side of a major fault.  
No shows of oil or gas were seen in this "test", therefore recommended  
that the "test" be plugged and abandoned without reaching original  
objective, the Hunton.

Plugged 1/13/74 with 12 sacks Common Cement at 200'; 6 sacks Common  
Cement at 30'.

CLARENCE MAAS #1 - SW SE NW of Section 27-12S-9E, Wabaunsee County, Kansas

(SOUTH YAEGE PROSPECT)

Drilling Contractor: Alco Drilling Co., Inc.  
Iola, Kansas 316-365-6013 (L. W. McClain, Pres.)

Manhattan, Ks. % ~~Traveller's Motel~~ 913-743-4836  
East Highway #24

Geologist:

INVESTORS:

*completed  
mailed  
intent  
12/13/73  
did not complete  
intent - not moving  
973-5351  
12/13/73  
Garage*

*Carney*  
Deitch, Jr.  
A. Kenneth J.  
Keith H. Jones  
Geo. Middleton  
Ralph H. Miller  
Terence Scanlon  
Merlin Casse

- 12/3/73 Filed "Intent to Drill" w/ State Corporation Commission. Ordered "staking and elevation to be run by Laughlin-Simmons today/ they will call & advise when they will be in area Rotary Tools will be moving in one (1) week from today/GNR, Ordered Certificate of Title from Reg. Deeds Office.
- 12/5 Lucille/Laughlin-Simmons thinks can stake Monday or Tuesday next week.
- 12/6 L. W. McClain returned our call/talked to GNR today.
- 12/7 Lucille/Laughlin-Simmons advised will stake and run elevation, Monday, 12/10/73
- 12/10 Lucille/Laughlin-Simmons called could hold off until later this week or could go tomorrow (Tuesday). GNRupe advised moving in Wednesday--so should be there on Tuesday for staking and elevation.
- 12/11 4:45 p.m. Called Lucille/Laughlin-Simmons and Bob is there today staking etc.--may require lots of walking--reason for taking full day. Hasn't heard from him yet today--but will call as soon as she does.

*L.W. McClain called advising want not get in to drill this year  
as per Bill Clement via GNRupe*

Laughlin-Simmons staked location today and ran elevation - 1304' Ground level.

- 12/13/73 Bulldozing a road and preparing to move in Rotary Tools.
- 12/14/73 <sup>p.m.</sup> Lewis McClain called/talked with GNR re another to enter location already staked Got moved in yesterday and broke down as per Bill Clement call to Mrs. McClain.

SOUTH YAEGE PROSPECT

JAMES G. MESEKE #1 - SE NE SW of Section 27-12S-9E, Wabaunsee County, Kansas

Drilling Contractor: Alco Drilling Co., Inc. Iola, Kansas 316-365-6013 (L. W. McClain, Pres.)  
Manhattan, Ks. % Travelers Motel #913-776-4836  
East Highway #24

Geologist: Wm. G. Clement  
Wichita, Kansas 264-3740

*(Lucy Rutter  
L. W. McClain)*

INVESTORS

- Deitch, Jr.
- A. Kenneth Jones
- Keith H. Jones
- Geo. Middleton
- Ralph Miller
- Terence Scanlon
- Merlin Cassell

- 12/18/73 Bill Clement called Alco Drlg. Iola, Ks. talked w/ Mrs. McClain yesterday advised got moved in/and broke down  
4:00 p.m. Ordered elevation run by Laughlin-Simmons. They will call back tomorrow to advise when can be done. Want it within 1 week
- 12/19 Bill Clement called Alco Office 9:00 a.m. -advised was waiting on cementer to set Surface Casing. Has call into Manhattan for McClain.  
3:00 p.m. Ordered elevation to be taken any time between Xmas & New Years
- 12/28/73 Lucille/Laughlin-Simmons called--talked to Bill--will get in to take 9:30 a.m. elevation either 1st or 2nd of January '74
- 1/2/74 - McClain called in talked to GNR--due to severe cold weather--will not be back in drilling for several days. (15 degrees below zero)
- 1/4/74 Bob Mosier/LAUGHLIN-SIMMONS called re taking elevation--talked to GNR. File Intent to begin drilling next Tuesday, 1/8/74 as per GNR today.
- 1/8/74 10:00 a.m. Mr. McClain called in advising started drilling out from under Surface at 7:00 p.m. last night/this morning at 2:00 a.m. drilling at 600'.
- 1/9/74 Drlg at 1250' at midnight last night.  
" at 1579' at 1:00 p.m. today.  
Bill Clement left for Manhattan at 5:00 p.m. staying Travelers Motel #913-776-4836)
- 1/10/74 10:45 a.m. Bill called in "collect" drilling at 1640' at midnight. Est. Elevation Gr. 1300'  
TOP HERBNER 1278' +25'  
TOP LANSING 1499' -199'  
(Running 276' low)  
(Laughlin-Simmons to call us when will take elevation)
- 1/11/74 11:45 a.m./Bill Clement called "collect" - drlg at 1825' midnight last night.  
( 5 degrees below zero)  
3:20 p.m. -Lucille/Laughlin-Simmons gave elevation as 1284'  
+ 4  
1288
- 1/14/74 Revised Sample Tops w/ Laughlin-Simmons

1/10/74 - Dick Foley called in/tell Bill Clement  
Foley talked to Glen Rupe about the Samples.  
that he ran.

*Joel Bell 1/10/74  
10:45 am*

1/13/74 - RTD 2380' D&A  
Plugged 1/13/74 -

Set 6 Sx Common

The #1 Meseke ran 800' low to the Wells to the West. This is rather conclusive evidence that the "test" is on the low side of a major fault. No shows of oil or gas were seen in this test. Therefore recommended that the...

SOUTH YAEGE PROSPECT

JAMES G. MESEKE #1 - SE NE SW of Section 27-12S-9E, Wabaunsee County, Kansas

Drilling Contractor: Alco Drilling Co., Inc.

Iola, Kansas 316-365-6013 (L. W. McClain, Pres.)

Manhattan, Ks. % Travelers Motel #913-776-4836 - Room 6  
East Highway #24

Geologist: Wm. G. Clement

Wichita, Kansas 264-3740

INVESTORS

Deitch, Jr.

A. Kenneth Jones

Keith H. Jones

Geo. Middleton

Ralph Miller

Terence Scanlon

Merlin Cassel

Lewis H. Humrey

Consolidated

12/13

12/18/73 Bill Clement called Alco Drlg. Iola, Ks. talked w/ Mrs. McClain  
yesterday advised got moved in/and broke down yesterday

4:00 p.m. Ordered elevation run by Laughlin-Simmons. They will call  
back tomorrow to advise when can be done. Want it within 1 week.

12/19 Bill Clement called Alco Office 9:00 a.m. -advised was waiting on cementer  
to set Surface Casing. Has call into Manhattan for McClain.

3:00 p.m. Ordered elevation to be taken any time between Xmas & New Years.

12/28/73 Lucille/Laughlin-Simmons called--talked to Bill--will get in to take  
9:30 a.m. elevation either 1st or 2nd of January '74.

1/2/74 - McClain called in talked to GNR--due to severe cold weather--will not be  
back in drilling for several days. (15 degrees below zero)

1/4/74 Bob Mosier/LAUGHLIN-SIMMONS called re taking elevation--talked to GNR.

File Intent to begin drilling next Tuesday, 1/8/74 as per GNR today.

1/8/74 10:00 a.m. Mr. McClain called in advising started drilling out from under Surface  
at 7:00 p.m. last night/this morning at 2:00 a.m. drilling at 600'.

1/9/74 Drlg at 1250' at midnight last night.

" at 1579' at 1:00 p.m. today.

Bill Clement left for Manhattan at 5:00 p.m. staying Travelers Motel #913-776-4836)

1/10/74 10:45 a.m. Bill called in "collect" drilling at 1640' at midnight. Est. Elevation Gr. 130

TOP HEEBNER 1275' +25'

TOP LANSING 1499' -199'

(Running 276' low)

(Laughlin-Simmons to call us when will take elevation)

1/11/74 11:45 a.m./Bill Clement called "collect" - drlg at 1825' midnight last night.

( 5 degrees below zero)

TOP KANSAS CITY 1609' -304'

3:20 p.m. -Lucille/Laughlin-Simmons called

BASE KANSAS CITY 1821' -521'

gave elevation as 1284' Ground level

+ 4'  
- 1288' Kelly Bushing

1/14/74 Revised Sample Tops w/ Laughlin-Simmons elevation:

TOP HEEBNER	1275'	+9'
TOP LANSING	1499'	-215'
KANSAS CITY	1619'	-335'
BASE KANSAS CITY	1841'	-557'

1/13/74 - RTD 2380' D&A

Plugged 1/13/74 - Set 12 sx Common @ 200' on plug.

Set 6 Sx Common @ 30' on plug.

The #1 Meseke ran 800' low to the Wells to the West. This is rather conclusive evidence  
that the "test" is on the low side of a major fault. No shows of oil/or gas were seen in this

SOUTH YAEGE PROSPECT

#1 - SE NE SW of Section 27-12S-9E, Wabaunsee County, Kansas

By: Alco Drilling Co., Inc.  
 Iola, Kansas 316-365-6013 (L. W. McClain, Pres.)  
 Manhattan, Ks. % Travelers Motel #913-776-4836 - Room 6  
 East Highway #24

Wm. G. Clement  
 Wichita, Kansas 264-3740

*(Leary Renter  
 Love case by)*

INVESTORS  
 Deitch, Jr.  
 A. Kepneth Jones  
 Keith H. Jones

*12/16 Moving In  
 12/17 49" surface hole. Broke down.  
 12/18 TO surface hole & ran 306' of 79 csg.  
 12/19 Waiting on Cementing. Shut down because of weather  
 will cement casing on 21st.  
 12/21 Cementing surface pipe. Will start up again  
 after holidays. 306' w/ 75 sp. on 12/21/73*

Bill Clement left for

1/10/74 10:45 a.m. Bill called in "collect" drilling at

TOP HEEBNER		
TOP LANSING	1499'	-199'

(Running 276' low)  
 (Laughlin-Simmons to call us when will take elevation)

1/11/74 11:45 a.m./Bill Clement called "collect" - drlg at 1825' midnight last night.

( 5 degrees below zero)

TOP KANSAS CITY	1609'	-309'
BASE KANSAS CITY	1821'	-521'

3:20 p.m. - Lucille/Laughlin-Simmons called

gave elevation as 1284' Ground level

1288' Kelly Bushing

1/14/74 Revised Sample Tops w/ Laughlin-Simmons elevation:

TOP HEEBNER	1275'	+9'
-------------	-------	-----

1/10/74 - Dick Foley called in/tell Bill Clement  
 Foley talked to Glen Rupe about the Samples  
 that he ran.

1/13/74 - RTD 2380' D&A  
 Plugged 1/13/74 -

Set 6 Sx Common @

*Joel Bell 1/10/74  
 10:45 am*

The #1 Meseke ran 800' low to the Wells to the West. This is rather conclusive evidence



SOUTH YAEGE PROSPECT

**RUPE OIL COMPANY**

JAMES MESEKE #1 - SE NE SW of Section 27-12S-9E, Wabaunsee County, Kansas

---

Drilling Contractor: Alco Drilling Co., Inc.  
Iola, Kansas

Geologist: William G. Clement  
Wichita, Kansas

---

December 14, 1973 - We had to change our Well location from the MAAS #1 to the above MESEKE #1 as the Drilling Contractor was unable to move in due to muddy roads, etc. at this time of year.

December 16, 1973 - Moving in Rotary Tools.

December 17, 1973 - Drilled 9" Surface hole--broke down.

December 18, 1973 - Ran 306' of 7" Surface Casing.

December

---