

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


21-13-1E

Company- JACK-DESBROW ET AL  
Farm- Garvie No. 1

SEC. 21 T. 13 R. 1E  
CS/2 N/2 SW

Total Depth. 3091  
Comm. 3-12-52 Comp. 3-27-52  
Shot or Treated.  
Contractor. E. K. Carey  
Issued. 7-12-52

County Dickenson  
KANSAS



CASING:  
8 5/8" 125' com. w/175 sx  
5 1/2" 3015' com. w/150 sx

Elevation. 1165 DF

Production. Dry

11561 3rd.  
1163 L & S

Figures indicate Bottom of Formations.

cellar	8
sand	53
sand	55
lime, shale	175
shale, lime	650
shale	840
shale, lime	1195
shale	1315
lime, shale	1470
lime	1565
lime, shale	1732
lime	1875
shale	1895
lime	2090
shale, lime	2341
lime	2587
shale	2715
lime	2912
shale	2998
lime	3015 RTD
lime	3091

Total Depth

Scout Tops:

Hunton	2715
Maquoketa Shale	2912
Viola	3002

Perf. 32 shots 3002-12, no  
results, perf 16 shots 2346-51'  
wtr

6-3-52 acid 1000 gals.  
32 perforations 3002-12 w/baker  
plug set 3014 and baker packer 2969  
no oil recovered, only wtr. no  
swabbing test.