

2-13-10E

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS


API# 16-177-00108
COMPANY SKELLY OIL COMPANY

SEC. 2 T. 13 R. 10E
LOC. SE NW SE
990' FNL, 990' FWL, SE

FARM Carl Thowe NO. 1

TOTAL DEPTH 3307
COMM. 7-14-50 COMP. 11-25-50
SHOT OR TREATED
CONTRACTOR Adkins Drlg Co., Inc.
ISSUED 2-10-51

COUNTY Wabaunsee
KANSAS



CASING
8 5/8" 200' cem w/110 sx
4 1/2" 3148' cem w/675 sx

ELEVATION 1104 (-m)
1110 DF
111 L S
PRODUCTION SWDW

FIGURES INDICATE BOTTOM OF FORMATIONS

lime, shale	0- 200	Slight odor with little porosity	1550-71
shale, lime, sand	659	Good odor and stain	2950-53
lime, shale	1252	Good odor	2953-56
lime	1315		
lime & shale	1525	7-30-50 Upon drilling to a depth of 3162 and after running Schlumberger to same depth; commercial production was not encountered. Filled hole w/rotary mud and well was temporarily abandoned.	
lime	1571		
lime, shale	2195		
lime, sand, shale	2225		
chert & lime	2435		
lime	2507	Perforated 8 5/8" OD casing from 93'95' w/6 holes by L-W Reg. Bullets, and cemented w/35 sx. to shut off gas which had commenced channeling out through formation behind 8 5/8" OD casing.	
shale	2709		
chert & lime	2735		
lime	2875		
shale	2950	11-24-50 Conditioned mud and drilled ahead to total depth 3307.	
lime	3060		
shale, sand, lime	3147	Arbuckle 3148 - 3307 Salt water disposal formation.	
lime	3162		
lime	3307	Casing: Measurements from top of rotary drive bushing to ground level - 5'.	
Total Depth			

Show gas, Towle sand 114-120 2.37 MCF/D

Pops:

Howard	588
Topeka	659
Lansing	1233
Kansas City	1379
Mississippi	2190
Kinderhook	2507
Hunton	2706
Maquoketa	2874
Viola	2950
Simpson Shale	3040
Simpson Sand	3060
Arbuckle	3144
Pre-Cambrian Granite	3290

DST #1 1550-1571; tool open 30 min.; rec. 960' of drilling mud & water w/no show oil. BHP 450#

DST #2 2950-2956; tool open 2 hrs; rec. 240' oil & 2770' water. BHP 1100#.

DST #3 2950-2956; tool open 1 hr & 15 min. recovered 120' oil & 2790' of brackish wtr. BHP 1100#. Gvty oil; 20.9 A.F.I. Corr.

Ran Schlumberger to 3162