

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

2-13-10E

COMPANY SKELLY OIL CO.

SEC. 2 T. 13 R. 10E

FARM Carl Thowe

NO. 3

LOC. NW NE SE

330' fr N.L. & 1650' fr W.L.
SE/4

COUNTY Wabaunsee

TOTAL DEPTH 2925

COMM. 12-1-50


COMP. 12-12-50

SHOT OR TREATED

CONTRACTOR Adkins Drlg. Co.

ISSUED 5-12-51

KANSAS



CASING

8 5/8" 204' cem. w/150 sx
5 1/2" 2917' cem. w/150 sx

ELEVATION 1099 DF

PRODUCTION Pmp. 78.44 BO
& NW in 8 hrs.

FIGURES INDICATE BOTTOM OF FORMATIONS

shale, sand & lime	210
shale & shells	566
shale & lime	1304
lime	1575
lime & shale	1770
shale, lime & sand	2204
lime & chert	2470
shale	2667
lime & chert	2760
lime	2839
shale & lime	2917
lime	2921
lime	2925
Total Depth	

Show gas, Towle sand, 105'-110'
15.4 MCF/D

Tops:	
Howard	559'
Topeka	625'
Lansing	1220
Kansas City	1364
Miss. Lime	2205
Kinderhook	2470
Hunton	2667
Maquoketa	2839
Viola	2917

Producing Formation --
2917' to 2921'

Main body of pay 2917'-2921'
Good coarse xyn dolomite with
good porosity and saturation.
2917'-2921'

Attempted DST: #1 - 2917'-2921';
failed to take due to tool
becoming blocked.

DST: #2 - 2917'-2921'; tool
open 1 hr.; rec. 350' free oil
and 10' oil cut mud & water.
Shut in B.H.P. after 15 min.
1072#.

Ran Schlumberger Survey to 2921'.

Above measurements from top
of rotary drive bushing to
ground level---5'