

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas


33-13-10E

API # 15-197-70001
Company - THE CARTER OIL COMPANY
Farm - G.H. Davis "A" No. 5

SEC. 33 T. 13 R. 10E
SW NE NW

Total Depth. 3203
Comm. 11-2-49 Comp. 1-11-50
Shot or Treated.
Contractor. Adkins Drilling Co., Inc.
Issued. 9-2-50

County. Wabaunsee
KANSAS



CASING:

10 3/4" 177' cem. w/125 sx

Elevation. 1425

1428.2nd.
Production. 3000 bbls. oil

Figures Indicate Bottom of Formations.

shale, sand & lime	187
lime & blue shale	250
shale & gypsum	310
shale & lime shells	455
recemented surface pipe	
cement	128
2 plugs and cement	145
open hole	180
cement & plug	189
open hole	455
shale & lime shells	800
shale, shells & sand	1045
lime & shale	1545
lime	1650
shale	1692
lime	1890
lime & shale	2110
shale	2167
sand & shale	2205
shale & lime	2260
shale	2320
shale, lime & sand	2415
shale & lime	2491
chert	2493
chert & lime	2640
chert	2658
lime & shale	2695
lime	2776
shale	2987
lime	3065
dolomite	3115
shale & dolomite	3140
shale	3175
cored 3175 to 3203	
lime	3203
Total depth	

Tops:	
Howard	906
Topeka	966
Lansing	1551
Kansas City	1692
Base Kansas City	1890
Cherokee	2167
Miss. lime	2503
Kinderhook	2776
Hunton	2969
Maquoketa	3102
Viola	3178